

# LONG ACRES ENVIRONMENTAL STATEMENT

VOLUME 2: CHAPTER 0  
MITIGATION AND MONITORING

**Long Acres, South Tees**  
**Volume 2: Environmental**  
**Statement (December 2020)**

**Chapter O: Mitigation and Monitoring**

**Lichfields**  
**The St Nicholas Building**  
**St Nicholas Street**  
**Newcastle upon Tyne**  
**NE1 1RF**

# Contents

<b>O1.0</b>	<b>Introduction</b>	<b>1</b>
	About the Author	2
<b>O2.0</b>	<b>Mitigation and Monitoring</b>	<b>3</b>
<b>O3.0</b>	<b>Summary &amp; Conclusions</b>	<b>19</b>
<b>O4.0</b>	<b>Abbreviations &amp; Definitions</b>	<b>20</b>
<b>O5.0</b>	<b>References</b>	<b>22</b>

## 01.0 Introduction

- 01.1 The Environmental Statement ('ES') has identified a series of mitigation and ongoing monitoring and/or management measures which are designed to limit or remove any significant adverse environmental effects of the proposed development.
- 01.2 Schedule 4, Part 7 of the Town and Country Planning (Environmental Impact Assessment) ('EIA') Regulations 2017 (as amended) ('2017 EIA Regulations (as amended)') (Ref 1) requires an ES to provide:
- "A description of the measures envisaged to avoid, prevent, reduce or, if possible, offset any identified significant adverse effects on the environment and, where appropriate, of any proposed monitoring arrangements (for example preparation of a post-project analysis)."*
- 01.3 The Planning Practice Guidance ("PPG") confirms that **"mitigation measures proposed in an Environmental Statement are designed to limit or remove any significant adverse environmental effects of a development. Local planning authorities will need to consider carefully how mitigation measures proposed in an Environmental Statement are to be secured"** [ref. Paragraph 051 Ref ID: 4-051-20170728].
- 01.4 In accordance with Regulation 26(3) of the 2017 EIA Regulations (as amended), the PPG further states that *"where it is considered appropriate that monitoring measures are attached to a planning permission, this can be achieved through the use of existing mechanisms such as planning conditions and planning obligations."* [ref. Paragraph 051 Ref ID: 4-051-20170728].
- 01.5 The ES has identified primary/embedded, secondary/additional and tertiary mitigation and monitoring relevant to the proposed development. The 'IEMA Environmental Impact Assessment Guide to Shaping Quality Development' Report (November 2015) (Ref 2) provides definitions of the three types of mitigation as follows, which have been used as a basis for categorising mitigation within this ES:
- "Primary mitigation is an intrinsic part of the project design – it should be described in the design evolution narrative and included within the project description. For example, reducing the height of a development to reduce visual impact.*
- Secondary mitigation requires further activity in order to achieve the anticipated outcome – typically, these will be described within the topic chapters of the ES, but often are secured through planning conditions and/or management plans. For example, description of certain lighting limits that will be subject to submission of a detailed lighting layout as a condition of approval.*
- Tertiary mitigation will be required regardless of any EIA assessment, as it is imposed, for example, as a result of legislative requirements and/or standard sectoral practices. For example, considerate contractors practices that manage activities which have potential nuisance effects".*
- 01.6 The primary and tertiary mitigation and monitoring for the proposed development are set out in Chapter B. The secondary mitigation measures are set out in Section 6.0 of each technical chapter of the ES.
- 01.7 Consideration has also been given in Chapter N as to the possibility of significant adverse impacts arising from either synergistic or cumulative effects and whether there is a requirement for further secondary mitigation to address these effects. Chapter N does conclude that there will be some significant adverse and beneficial cumulative effects, when the proposed

development is considered alongside other cumulative schemes. It therefore identifies that there will be a need for further secondary mitigation and this is discussed in Section O2.0 below.

- O1.8 This chapter summarises all mitigation measures proposed throughout the ES for ease of reference, along with the mechanism(s) for securing these. It should be used to assist RCBC] in forming their reasoned conclusion of the proposed development.

### **About the Author**

- O1.9 This ES has been coordinated by Katie Brown, Heather Overhead and Melissa Wilson all Senior Planners at Lichfields. Katie is a Practitioner Member of the Institute of Environmental Management and Assessment ('IEMA') and has 3 years' experience in co-ordinating EIAs for a range of major development projects across the United Kingdom ('UK'). Heather is working towards her EIA Practitioner membership of IEMA and has 1 year of experience in EIA projects. Melissa is working towards her EIA Practitioner membership of IEMA and has 2 years of experience in EIA projects. Their coordination role included the production of this chapter of the ES, with input from the wider technical project team.
- O1.10 Kate McGill, Associate Director at Lichfields, and Practitioner Member of IEMA, has reviewed this chapter in accordance with the EIA Regulation requirements. Kate has over 10 years of experience of co-ordinating EIAs for a range of development projects.

## O2.0 Mitigation and Monitoring

- O2.1 As set out in Chapter B of this ES, the iterative process of EIA has resulted in the incorporation of a range of ‘built-in’ mitigation measures into the design of the proposed development. These are aspects of the design which have been specifically included in the scheme design and are assumptions on which the assessment and resultant additional mitigation have been based.
- O2.2 Tables O2.1 and O2.2 set out the primary and tertiary and secondary mitigation and monitoring measures respectively proposed throughout the technical chapters of the ES and set out within Chapter B. The tables also set out the means by which the mitigation can be secured, including whether there will be a requirement to submit a mitigation and or monitoring documents or adhere to an issue-specific condition and clarifies responsibility for implementing the proposed mitigation and monitoring.
- O2.3 In considering how best to secure the mitigation and monitoring measures, consideration has been given to paragraph 56 of the National Planning Policy Framework (Ref 3). This states that: *“Planning conditions must only be sought where they meet all of the following tests:*
- a *Necessary to make the development acceptable in planning terms;*
  - b *Directly related to the development; and*
  - c *Fairly and reasonably related in scale and kind to the development”.*
- O2.4 It is also noted that required monitoring measures can also be attached via planning conditions or planning obligations, as long as any provisions used are clear and precise and ensure clarity for all parties concerned.

Table O2.1 Summary of Primary/Tertiary Mitigation

Summary of Identified Primary/Tertiary Mitigation	Means of Securing	Responsibility
<b>During Construction</b>		
Implementation of a Framework Construction Environmental Management Plan (‘CEMP’) which sets details on a range of matters including: <ul style="list-style-type: none"> <li>a. Best practice site works principles;</li> <li>b. Relevant risk assessment method statements (‘RAMS’);</li> <li>c. Details on requirements for supporting documents including; Construction Logistics Plan (‘CLP’), Construction Traffic Management Plan (see below), Dust Management plan (‘DMP’), Construction Stage Surface Water Management Plan; Health and Safety Plan (‘HSP’);</li> <li>d. Removal of trees, scrub and wetland habitat or grassland; and</li> <li>e. Measures to prevent the spread of invasive non-native plant species.</li> </ul> Full details of the site-wide CEMP principles can be viewed in paragraphs B7.32- B7.33 in Chapter B of the ES.	Framework CEMP submitted with the application. The following will be secured by way of a Planning Condition: <ol style="list-style-type: none"> <li>1. RAMS;</li> <li>2. Construction Logistics Plan;</li> <li>3. Dust Management Plan;</li> <li>4. Health and Safety Plan;</li> <li>5. Construction Stage Surface Water Management Plan.</li> </ol>	Applicant/ Principal Contractor
Implementation of a Construction Traffic Management Plan (‘CTMP’) as part of the CEMP.	CTMP submitted as part of the CEMP or separately	Applicant and Principal

Summary of Identified Primary/Tertiary Mitigation	Means of Securing	Responsibility
	and secured via Planning Condition.	Contractor.
Further ground investigation surveys will be undertaken in order to identify the need, or otherwise, for additional remediation work. This stage of work, if necessary, will include the submission of details to divert the Fleet and any associated ground remediation necessary as part of the diversion.	Ground Investigation Survey secured via Planning Condition.	Applicant and Principal Contractor.
The hydrology of Coatham Marsh will not be affected by any works to the Fleet. A method statement for assessing works to alter or realign the on-site watercourses demonstrating this shall be submitted and approved by the Local Planning Authority prior to the approval of any detailed scheme of works to the watercourses.	Method Statement for works to the watercourse secured via a planning condition.	Applicant and Principal Contractor.
All temporary construction works will be designed to meet engineering and health and safety standards.	Outwith planning/ accordance with health and safety legislation	Applicant and Principal Contractor.
The site is to be cut and fill neutral, ensuring the reuse of suitable excavated materials generated on site is maximised.	Planning Condition.	Applicant and Principal Contractor.
Protective fencing to be erected around land not being developed	Fencing details to be secured via Planning Condition.	Applicant and Principal Contractor.
Setting up of construction compounds and waste, fuel and storage areas ahead of construction work commencing. Materials for active phase of development only to be stored onsite.	Planning Condition.	Applicant and Principal Contractor.
Hazardous and non-hazardous waste to be sent to the Highfield landfill site.	Planning Condition Or legal obligation.	Applicant and Principal Contractor.
A Piling Risk Assessment is to be prepared for each phase of the development.	Piling Risk Assessment secured via Planning Condition.	Applicant and Principal Contractor.
The scheme will seek to be BREEAM 'Very Good'. The sustainability credentials of the scheme will be agreed at reserved matters stage of the planning process, however those considered to be embedded during construction include: <ul style="list-style-type: none"> <li>a. Contractors will use local suppliers, or sourcing materials from the Teesworks areas and they will be required to implement a Site Waste Management Plan (SWMP) which will be monitored throughout the construction period; and,</li> <li>b. All building materials and products will be sourced, where practical from suppliers who manufacture with certified environmental management systems and timber will be Forest Stewardship Council (FSC) certified, where possible.</li> </ul>	BREEAM Very Good Rating requirement to be secured via Planning Condition.  Specific information also included within the SWMP (also to be secured via Planning Condition).	Applicant and Principal Contractor.

Summary of Identified Primary/Tertiary Mitigation	Means of Securing	Responsibility
<b>During Operation</b>		
<p>The Parameters Plan provides for the following:</p> <ol style="list-style-type: none"> <li>1. Maximum development area is 62.33ha;</li> <li>2. Maximum development height across the site is 43.5m AOD;</li> <li>3. Maximum building height is 36m above the prevailing ground levels;</li> <li>4. A minimum of 1 vehicular access point into the site; for the purposes of this EIA, it is assumed that the access will be on the south side of the site and will connect to the public highway network at the Steel House roundabout, also known as the Trunk Road roundabout which is on the A1085 Trunk Road. The Parameters Plan submitted to accompany this EIA (Appendix B3) shows the location of the access point into the site together with areas where other potential access points could be formed into the site from the surrounding internal estate roads.</li> </ol>	Detailed within Planning Condition.	Applicant
The proposed development will comprise up to 185,806sqm B2, B8, and E floorspace.	Planning Condition.	Applicant
Buildings within the site will meet BREEAM 'Very Good' standard	Planning Condition	Applicant
A Framework Travel Plan ('FTP') and specific Occupier Travel Plans ('OTP') will be prepared to support and promote sustainable modes of travel in accordance with STDC's emerging transport strategy. A dedicated bus service will be provided to connect the local towns of Middlesbrough and Redcar to the development site.	FTP/OTP to be implemented and secured via Planning Condition/Planning Obligation.	Applicant and future Occupiers.
Junctions and internal roads to be designed and constructed in accordance with Redcar and Cleveland Borough Council Guidance.	Planning Condition	Applicant
To comply with COMAH and HSE guidance, where necessary, the levels of occupancy of buildings will be restricted and stand-off distances from hazardous installations, pipes etc will be imposed.	Planning Condition/Planning Obligation.	Applicant / RCBC

Table O2.2 summary of Secondary Mitigation

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
<b>During Construction</b>			
Transport	No mitigation measures are required during construction above those set out within the CEMP and CTMP	N/A	N/A
Biodiversity and Ecology	<p>A reptile mitigation strategy will be prepared. The reptile mitigation strategy shall include measures to prevent harm to reptiles and to maintain the population of reptile’s ex-situ. It will include a specific monitoring programme to ensure that the objectives of the strategy have been achieved.</p> <p>The recommendations of the reptile mitigation strategy will be implemented in accordance with the phasing therein.</p> <p>No effects on habitats and species are anticipated during operation therefore no further mitigation is proposed.</p>	Reptile Mitigation Strategy secured via a Planning Condition.	Applicant/ Principal Contractor.
Noise and Vibration	No mitigation required, other than a Risk Assessment to identify the probability of noise and vibration from any piling or compaction activities and construction traffic. This will determine the need for any periodic or continuous noise or vibration monitoring.	Noise and vibration Piling Risk Assessment secured via Planning Condition- as set out in Table O2.1 above.	Applicant/ Principal Contractor
Air Quality	<p>No mitigation measures are required during construction.</p> <p>Once details on the scheme are known, the assessment of construction traffic will identify the need for any specific mitigation measures.</p>	N/A	N/A
Water Management and Flooding	A site-specific Drainage Strategy will inform the details of the CEMP/Construction Stage Surface Water Management Plan.	Drainage Strategy secured via Planning Condition	Applicant and Principal Contractor.
	Appropriate measures to be agreed with the Council to manage localised depressions on site, which results in areas of pluvial flooding at high rainfall events until the ground surface is constructed.		
	<p>The timing of excavation and replacement of ground materials shall be sensitive to avoiding poor weather conditions.</p> <p>Placement of oil-water interceptors at outfalls from the site</p>	<p>Planning Condition</p> <p>Planning Condition</p>	<p>Applicant and Principal Contractor.</p> <p>Applicant and Principal</p>

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
			Contractor.
	A Construction phase Groundwater Management Plan will be prepared and submitted to the LPA to avoid any adverse impacts on SPA / SSSI/Ramsar designations.	Ground Water Management Plan secured via a Planning Condition	Applicant and Principal Contractor.
Ground Conditions and Remediation	A detailed remediation strategy for each phase shall be prepared and agreed with the LPA. The detailed remediation strategy should be in accordance with the outline strategy.	Detailed remediation strategy secured via a Planning Condition	Applicant and Principal Contractor.
	A strategy for dealing with Unforeseen Contamination shall be agreed with the LPA.  Where unanticipated contamination is encountered within excavated material that is similar to that encountered elsewhere within the site, then the process set out below will be followed:  <ol style="list-style-type: none"> <li>1. Sampling for, and undertaking chemical analysis;</li> <li>2. Assessment of chemical data; and,</li> <li>3. Sentencing for remediation and/or processing, as necessary.</li> </ol> Where identified environmental contamination extends below 2.5m bgl, any requirement for deeper excavation works will be assessed on a case specific basis following consultation with stakeholders.  The location of any such unanticipated contamination encountered will be recorded, including the results of chemical testing, the volumes sentenced for treatment by remediation, the validation data showing compliance with the relevant remediation objectives and the location of the area of reuse of the remediated material within the development platform.	Contamination investigations, Risk Assessment and remediation and recording scheme (if required) secured via a Planning Condition.	Applicant and Principal Contractor.
	Additional ground gas monitoring at greater density is recommended prior to any specific redevelopment to determine the risk from ground gases on the site.	Planning Condition.	Applicant and Principal Contractor.
	Further mitigation activities such as Detailed Risk Assessment or site mitigation to reduce the UXO risk on the site to As	UXO Risk Assessment secured via a Planning	Applicant and Principal

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
	<p>Low As is Reasonably Practicable (ALARP)</p> <p>Implementation of asbestos removal best practice should asbestos be encountered during groundworks.</p> <p>In the event that suspected materials are observed associated with excavations, sampling will be undertaken to confirm the asbestos type and quantification. Where Asbestos Containing Materials (ACM) have to be removed to facilitate the removal of structures it shall be separately stockpiled and covered to control potential dust generation. Any soils containing asbestos that are also in excess of the remediation reuse criteria will not be subject to mechanical screening where free fibres have been detected or are suspected. Where necessary soils containing asbestos will be managed by maintaining mist sprays to keep the soils wet whilst handled and may also be covered when stockpiled if necessary.</p> <p>In the event that materials are impacted with visible fragments of ACM, the ACM materials shall be handpicked by a suitably licenced asbestos contractor with additional control measures implemented based on the sampling results. Where soils containing Contaminants of Concern (CoC) in excess of the reuse criteria and, due to the presence of asbestos cannot be safely handled or successfully treated, they will be disposed of offsite. Where concentrations are below the reuse threshold soils may be reused as infill to excavation voids at depths below 0.6 m of final ground level.</p> <p>Asbestos should be presumed to be within all Made Ground deposits, and therefore will need to be included in a foundation works risk assessment.</p>	<p>Condition.</p> <p>Planning Condition.</p>	<p>Contractor.</p> <p>Applicant and Principal Contractor.</p>
	<p>To reduce the material going to landfill, a Deposit for Recovery permit would be obtained for re-use of the material within Warrenby CLE31 landfill. Use of the CL: AiRE DoWCoP (Definition of Waste: Code of Practice) and associated Materials Management Plan will be adopted for materials outside the landfill area, subject to regulatory approval.</p>	<p>MMP secured via Planning Condition.</p>	<p>Applicant and Principal Contractor and/or Reclamation / earthworks contractor</p>

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
	As part of the plan the records of all materials movements on-site and off-site will be kept by the Reclamation / Earthworks Contractor in paper and electronic format for a minimum period of 2 years following completion of the works and production of the Validation / Verification Report.		
Socio-Economic	<p>No mitigation measures are required during construction.</p> <p>Notwithstanding the above, STDC is committed to working with Redcar &amp; Cleveland Borough Council, where possible, to deliver training and apprenticeship schemes during the construction phase. It is anticipated that this will help to maximise the extent to which the beneficial effects of the development proposals are captured within the Area of Impact (AOI)</p>	<p>N/A</p> <p>Potential Planning Obligation</p>	<p>N/A</p> <p>Applicant / RCBC</p>
Climate Change	<p>The following opportunities are to be identified as proposed development proposals for the site continue to be developed:</p> <ol style="list-style-type: none"> <li>1 Further design iteration to reduce the absolute quantities of construction materials through efficient design and use materials with a lower carbon intensity where possible.</li> <li>2 Specification to reduce the embodied carbon of building materials and components e.g. through cement replacement and preferences for readily available products with higher recycled content.</li> <li>3 Maximised use of offsite construction for efficiency of material use and reduced construction waste.</li> <li>4 Challenges during procurement to encourage supply chains to provide products and materials with high recycled content.</li> <li>5 Application of circular economy principals to maximise the quantity of recycled and reused materials.</li> <li>6 Preference for materials and components that are locally sourced to minimise transportation distances</li> <li>7 Use of lower emissions vehicles for transporting materials to site where</li> </ol>	<p>Implemented through the application of wider sustainability principles to the proposed development as part of the CTMP and MMP, BREEAM Very Good all secured by way of a planning condition.</p>	<p>Applicant</p>

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
	<p>possible</p> <p>8 Construction Traffic management plan to minimise the number of journeys required.</p> <p>9 Use of electrical plant over fossil fuelled construction plant.</p> <p>10 Offsite construction/manufacturing for energy efficient assembly and minimising site installation processes.</p>		
Below Ground Heritage	<p>A programme of evaluation will be undertaken to identify any remains of 19<sup>th</sup> century iron works, medieval salt working, the duck decoy and World War II defensive structures. This should initially involve monitoring of site investigation test pits and where required, be followed by archaeological evaluation in the form of trial trenches.</p> <p>The Redcar blast furnace bases should be inspected, and a methodology drawn up for cleaning and recording. Should elements of the Coatham blast furnace bases, the duck decoy or the medieval salterns be found to survive on site, a programme of targeted excavation and recording would ensure preservation by record of the site type.</p>	Planning Condition	Applicant and Principal Contractor
	<p>The World War II defensive features should be recorded where upstanding and where buried, could be adequately recorded in an evaluation without the need for further excavation.</p>	Planning Condition	Applicant and Principal Contractor
	<p>A programme of archaeological monitoring (watching brief) should also be undertaken during remediation and, potentially, ground preparation work to allow identification and recording of other elements of the 19<sup>th</sup> century iron works.</p>	Planning Condition	Applicant and Principal Contractor
Landscape and Visual Impact	<p>The following mitigation measures are proposed during the construction phase of the development:</p> <p>1 Installation of suitable site hoarding, for example a 2.4, timber site hoarding with a plastic wrap incorporating appropriate graphics;</p> <p>2 Careful siting and management of materials stockpiles to reduce prominence on site by limiting the</p>	Planning Condition	Applicant.

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
	<p>height and volume of material stored on site; and</p> <p>3 Sensitive siting of site welfare and other temporary structures within the site compound.</p>		
Waste and Materials Management	<p>Generation of the scheme (and zone) specific architecture associated with the re-use of site-won materials and generation of earthworks wastes.</p> <p>A Deposit for Recovery Permit will be sought for the reuse of waste excavated from the CLE31 landfill</p>	Planning Condition	Applicant / Principal Contractor
	<p>Develop mechanisms to re-use site won materials through the use of:</p> <p>1 Utilising site-won materials generated during the development from earthworks;</p> <p>2 Reviewing opportunities to utilise excavated materials from other developments in proximity, using a Materials Management Plan under DoW CoP;</p>	Planning Condition and through MMP CWMP secured via a Planning Condition	Applicant / Principal Contractor
	<p>Develop a CWMP. Full details of the measures and targets to be included are in paragraph M6.4 - M6.6 of this ES.</p>	CWMP secured via a Planning Condition	Applicant / Principal Contractor
	<p>Sustainable management of wastes requiring treatment and/ or off-site disposal to minimize waste going to landfill and demonstrate end-of-waste.</p>	Planning Condition	Applicant / Principal Contractor
	<p>The use of secondary aggregates and recycled materials will be sought out where possible, with a target of 30% of construction materials required for the proposed development of each phase to be recycled and/or secondary, unless otherwise agreed in writing.</p>	Planning Condition	Applicant / Principal Contractor
	<b>During Operation</b>		
Transport	<p>The following mitigation measures are proposed:</p> <p>3 Occupier Travel Plan for each of the end occupiers at the development site;</p> <p>4 Wider travel planning measures, to reduce development traffic, encourage sustainable travel and the</p>	OTP secured via Planning condition or Obligation.	Applicant.

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
	<p>decarbonisation of the transport network (for example ensuring footway and cycleway connections are provided, providing secure cycle parking, providing staff up to date information on public transport services and walking/cycling provisions, promotions such as National Travel Awareness day and a 'Walking Buddy' Scheme, promoting car sharing, and consolidating servicing trips and deliveries);</p> <p>5 A review of traffic signals to see if junctions can be optimised (at the A66 / Eston Road junction and the A66 / Normanby Road signalised crossroads); and</p> <p>6 Potential junction improvements for the A66 / Tees Dock Road Roundabout and Greystones Roundabout.</p> <p>In addition to the above, and whilst a commitment cannot be made at this stage of the planning process, once adopted the emerging STDC Transport Strategy may provide an opportunity to further reduce the impacts of the proposed development on the sensitive receptors.</p>	Potential Planning Obligation/Condition	Applicant / RCBC
Biodiversity and Ecology	No effects on habitats and species are anticipated during operation therefore no further mitigation is proposed.	N/A	N/A
Noise and Vibration	Building services plant is envisaged to be placed at roof level. The specification of plant machinery with low noise emission and properly attenuated supply and extract terminations. The use of enclosures, local screening, mufflers and silencers should also be used as appropriate.	Planning Condition requiring submission of details of plant and accordance with noise guidance.	Applicant
	<p>The following mitigation of on-site activities will help to ensure the noise emissions are minimised in accordance with noise guidance</p> <ul style="list-style-type: none"> <li>- Noisy plant or equipment shall be situated as far as possible from any noise sensitive buildings.</li> <li>- Plant shall be maintained in good working order so that extraneous noise is kept to a minimum; and</li> <li>- An appropriate speed limit will be implemented for on-site vehicle</li> </ul>	Planning Condition	Applicant

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
	<p>movements, i.e. 10mph.</p> <p>Operational noise would therefore be kept at or below the existing ambient noise levels, preventing any significant effects of noise.</p>		
Air Quality	There are no significant effects predicted as a result of the operational phase of the development on air quality and therefore no mitigation measures are required.	N/A	N/A
Water Management and Flooding	<p>The following documents will be prepared:</p> <ul style="list-style-type: none"> <li>- A detailed Flood Risk Assessment ('FRA') and Drainage Impact Assessment ('DIA') with drainage strategy (for both foul and surface water);</li> <li>- Surface Water Management Plan ('SWMP'); and</li> <li>- A WFD Assessment.</li> </ul> <p>A detailed FRA and Drainage Impact Assessment with drainage strategy for foul and surface water will be prepared for each phase of the proposed development.</p> <p>The drainage strategy shall:</p> <ul style="list-style-type: none"> <li>- include consideration of design features to remove silt and other suspended solids, as well as capture any spills/oil and grease, prior to discharge. The large extent of low permeability surface proposed for the site will 'cap' underlying contaminated land.</li> <li>- not include infiltration SuDS such as soakaways, in order to limit mobilisation of contamination.</li> <li>- set out how to accommodate any groundwater input to the culverts that are present at the site;</li> <li>- protect any harvested rainwater for re-use so that it is not contaminated;</li> <li>- Accord with:                             <ul style="list-style-type: none"> <li>o Construction Industry Research and Information Association ('CIRIA') The Sustainable Drainage Systems ('SuDS') Manual C753;</li> <li>o Sewers for Adoption;</li> <li>o Local Authority SuDS</li> </ul> </li> </ul>	FRA and Drainage Impact Assessment, SWMP and WFD Assessment secured via Planning Condition / Environmental Permitting	Applicant

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
	<p style="text-align: center;">Officer Organisation Practice Guidance</p> <ul style="list-style-type: none"> <li>○ Tees Valley Local Authorities Local Standards of Sustainable Drainage</li> </ul> <ul style="list-style-type: none"> <li>- Where reasonably practicable the runoff rate from the site shall be reduced as far as possible in line with drainage guidance (noted in Section 6.4 a) in light of the large extent of low permeability surfaces;</li> <li>- take account of climate change projections (additional rainfall and surface water flows) and comply with current best practice;</li> <li>- Be based on Hydraulic modelling;</li> <li>- Ensure that drainage channels and/or networks and storage features will be lined with a geomembrane to prevent connection of surface water with contaminated ground material;</li> <li>- be sympathetic to the Teesmouth and Cleveland SSSI / SPA / Ramsar designation which includes Dabholm Cut and Dabholm Gut and works permits will require liaison with the Environment Agency and Natural England.</li> <li>- For any additional discharges, ensure a flap on the outfall to control the tidal influences, however it is anticipated that additional discharges to the Tees, if applicable, will be regulated under an environmental permit (and liaison with the Environment Agency and Natural England required where works are in relation to SSSI/ SPA/ Ramsar designations).</li> </ul> <p>Implementation of the SuWMP for each phase of the proposed development will improve the management of water compared to the baseline conditions, whilst also taking into account potential changes in rainfall from climate change.</p> <p>Changes to the water courses will be</p>		

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
	<p>applied and signed off via the Environmental Permit process.</p> <p>Once the site design is available, a WFD Assessment shall be undertaken for the entire site and then for each phase of the development the WFD Assessment should be updated</p> <p>Infrastructure on or under the site that does not have the required capacity will be required to be replaced / improved to meet guidance and planning requirements.</p>		
	<p>In order to avoid adverse impacts upon the SPA during the construction phase of the proposed development, a construction phase Groundwater Management Plan ("GWMP") will be submitted to the Local Planning Authority prior to any construction works taking place. This will be informed by the groundwater monitoring programme and shall demonstrate that the construction of the proposed development doesn't alter the hydrological characteristics of the SPA and thus avoids any adverse future impacts upon it.</p>	<p>Groundwater Management Plan secured via a Planning Condition</p>	
	<p>Ash Gill Beck and Steel House Lake are Ordinary Watercourses, therefore proposed discharge rates (if any) must be agreed with the LLFA and if required confirmation obtained for capacity of discharge to Northumbrian Water systems. This will be dealt with at the Reserved Matters stage of the planning process once the detailed design of the scheme is known.</p>	<p>Planning Condition / Environmental Permitting</p>	<p>Applicant</p>
	<p>Any works carried out to The Fleet shall not change the hydrology characteristics of Coatham Marsh unless it can be demonstrated that there would be no likely significant effect on the SPA arising from the final scheme of works for the Fleet.</p> <p>A remediation strategy shall be submitted and approved that ensures any highly contaminated soils are removed in proximity to the proposed realignment of The Fleet.</p> <p>A phasing plan of the works to realign The</p>	<p>Remediation Strategy and Phasing Plan secured via a Planning Condition / Environmental Permitting</p>	<p>Applicant</p>

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
	Fleet shall be submitted to and approved which confirms the timing of all works to realign The Fleet occur at an appropriate time (i.e. seasonal constraints of specific SSSI/SPA and/or Ramsar bird species) to avoid potential related pollutants occurring in the SSSI/ SPA and/or Ramsar.		
Ground Conditions and Remediation	The operational phase has been scoped out in relation to ground conditions and remediation as such there are no mitigation measures required.	N/A	N/A
Socio-Economic	<p>No mitigation measures are required during operation.</p> <p>However, STDC is committed to working with Redcar &amp; Cleveland Borough Council to deliver training and apprenticeship schemes, where possible, during the operational phase. Through the launch of the Teesworks Skills Academy – a hub set up to coordinate training and recruitment for employees across the Teesworks area – it is anticipated that this will help to maximise the extent to which the beneficial effects of the development proposals are captured within the AOI.</p>	<p>N/A</p> <p>Potential Planning Obligation</p>	<p>N/A</p> <p>Applicant / RCBC</p>
Climate Change	<p>Detailed design of buildings and facilities should adopt whole life assessments for the main building materials and systems to understand full impacts and replacement cycles.</p> <p>Maintenance plans should be informed by a Life Cycle Costing exercise.</p>	Planning Condition	Applicant and Future Occupiers
	<p>Development and Implementation of an Operational Energy Strategy that includes the installation of low and zero carbon technologies to provide lower carbon energy to the proposed development.</p> <p>Construction of energy efficient buildings to minimise energy demand.</p> <p>Ongoing engagement with the energy supply company to promote future transitions to low and zero carbon heat/power sources.</p> <p>Encouraging procurement of energy efficient equipment within the proposed development.</p> <p>Development of a comprehensive suite of</p>	Planning Condition/Obligation	Applicant and Future Occupiers (RBCB)

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
	transport measures to reduce reliance on cars by staff, and to encourage active and low carbon transport choices.		
Below Ground Heritage	No mitigation or monitoring is required during the operational phase of the development.	N/A	N/A
Landscape and Visual Impact	<p>Buildings to be articulated in a way which reduces visual scale and massing. Buildings to be stepped down to site boundaries to reduce the perception of massing in local and mid-range views and site layouts to present legible blocks of development with appropriate breaks to reduce visual impact.</p> <p>Building colour and cladding to be appropriate to surrounding colour palette, and help break up the visual massing, avoiding overly reflective materials. Use of colour gradation in the largest buildings to reduce the perception of height and massing in mid and long-range views. Buildings on individual plots to have a sensitive and complementary palette of materials and cladding to enable the development to be read as separate blocks in mid to long-range views.</p>	Planning Condition	Applicant
Waste and Materials Management	<p>An Operational Waste Management Plan (OWMP) shall be prepared and approved by the Council for each phase of the proposed development.</p> <p>This OWMP should consider the whole process of waste management including storage, collection, waste transport, treatment and disposal and include the following mitigation:</p> <ul style="list-style-type: none"> <li>- Provision of adequate internal storage space and containers for office units;</li> <li>- Residual and recyclable office wastes to be stored and collected separately via provision of clearly marked and/or colour-coded bins aligned with the local authority's guidance and infrastructure;</li> <li>- Provision of recycling facilities within the proposed development (i.e. card compactors, woodchippers/ pelletizers, etc.); and</li> </ul>	OWMP secured via a Planning Condition	Applicant

Environmental Topic	Summary of Secondary Mitigation	Means of Securing	Responsibility
	<ul style="list-style-type: none"> <li>- Provision of education and awareness to end-users on recycling and waste reduction.</li> </ul> <p>The OWMP should include recycling targets in line with The Tees Valley Joint Waste Management Strategy 2020-2035 which states that the region has in place a 60% recycling target for MSW and C&amp;I wastes by 2030.</p>		

- O2.5 Chapter N of the ES considered the requirement for additional mitigation to address any synergistic or cumulative effects. It was noted that a detailed site wide energy strategy shall be developed and that there are ongoing discussions regarding other potential transport mitigation measures.
- O2.6 The technical chapters of this ES have not identified the need for monitory contributions to be secured via S106 Agreement. This will be agreed with RCBC during the determination of the planning application.
- O2.7 The assessment in each technical chapter is based on the outline development parameters set out within Chapter B of this ES and based on professional experience and industry standard. Where assumptions have been made, further assessments may be necessary once the detailed scheme is known.

## 03.0 **Summary & Conclusions**

- 03.1 This ES sets out the finding of an EIA of proposals for up to 185,806 sqm of general industrial and storage or distribution facilities floorspace, with ancillary office accommodation, parking and associated works.
- 03.2 The ES has assessed the potential for the effects in relation to the following environmental matters:
- 1 Transport;
  - 2 Biodiversity and Ecology;
  - 3 Noise and Vibration;
  - 4 Air Quality;
  - 5 Water Management and Flooding;
  - 6 Ground Conditions and Remediation;
  - 7 Socio-Economic;
  - 8 Climate Change;
  - 9 Below Ground Heritage
  - 10 Landscape and Visual Impact; and,
  - 11 Waste and Materials Management.
- 03.3 The ES has also considered the possibility of impacts arising from either synergistic or cumulative effects. This chapter summarises the range of mitigation and monitoring measures have been identified throughout the ES.
- 03.4 These measures are largely capable of being enforced through planning conditions, either as part of management documents as standalone conditions or obligations, financial contributions secured via s106 agreement, or other non-financial obligations.
- 03.5 During the construction phase there are limited residual **Significant Adverse** Biodiversity and LVIA effects and **Significant Beneficial** Socio-Economic effects. During the Operational Phase, there are **Significant Adverse** LVIA effects and **Significant Beneficial** Socio-Economic and Water Management and Flooding effects. All other environmental effects assessed in Chapters C to M are considered to be Not Significant.
- 03.6 This ES has been based on high level development parameters for the outline scheme. During the detailed design stage and the reserved matters process, environmental considerations will be revisited as required by the 2017 EIA Regulations, and where necessary, updated as part of future submission to RCBC.

04.0

## Abbreviations & Definitions

- 1 ACM – Asbestos Containing Material
- 2 ALARP – As Low As is Reasonably Practicable
- 3 AOD – Above Ordnance Datum
- 4 AOI – Area of Impact
- 5 BREEAM – British Research Establishment Environmental Assessment Method
- 6 CEMP – Construction Environmental Management Plan
- 7 C&I – Commercial and Industrial
- 8 CIRIA – Construction Industry Research and Information Association
- 9 CL:AIRE – Contaminated Land: Applications in Real Environments
- 10 CLP - Construction Logistics Plan
- 11 CoC – Contaminant of Concern
- 12 COMAH – Control of Major Accident Hazards
- 13 CTMP – Construction Traffic Management Plan
- 14 CWMP - Construction Waste Management Plan
- 15 DIA – Drainage Impact Assessment
- 16 DMP - Dust Management Plan
- 17 DoWCoP – Definition of Waste: Development Industry Code of Practice
- 18 EIA - Environmental Impact Assessment
- 19 ES - Environmental Statement
- 20 EQS – Environmental Quality Standards
- 21 FRA – Flood Risk Assessment
- 22 FSC – Forest Stewardship Council
- 23 FTP – Framework Travel Plan
- 24 HSE – Health and Safety Executive
- 25 HSP - Health and Safety Plan
- 26 IEMA – Institute of Environmental Management and Assessment
- 27 LLFA – Lead Local Flood Authority
- 28 MMP – Materials Management Plan
- 29 MSW – Municipal Solid Waste
- 30 OTP – Occupier Travel Plans
- 31 OWMP – Operation Waste Management Plan
- 32 PPG – Planning Practice Guidance
- 33 RAMS – Risk Assessment Method Statement
- 34 RCBC – Redcar and Cleveland Borough Council
- 35 STDC – South Tees Development Corporation

- 36 SuDS – Sustainable Drainage Systems
- 37 SWMP - Site Waste Management Plan
- 38 SuWMP - Surface Water Management Plan
- 39 UK – United Kingdom
- 40 UXO – Unexploded Ordnance
- 41 WFD – Water Framework Directive
- 42 WSI – Written Scheme of Investigation

05.0

## References

- 1 Town and Country Planning (Environmental Impact Assessment) Regulations 2017 (as amended by the Town and Country Planning and Infrastructure Planning (Environmental Impact Assessment) (Amendment) Regulations 2018, which be viewed at:  
<https://www.legislation.gov.uk/uksi/2017/571/contents/made> and  
<https://www.legislation.gov.uk/uksi/2018/695/made>
- 2 IEMA Environmental Impact Assessment Guide to Shaping Quality Development' Report (November 2015), which can be viewed at:  
<https://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=&cad=rja&uact=8&ved=2ahUKEwje-JzLoI7sAhU2VBUIHY6uBHIQFjABegQIAhAB&url=https%3A%2F%2Fwww.iema.net%2Fdownload-document%2F7018&usg=AOvVaw3LuxxpYUJFEt19H6oB7Zh>
- 3 National Planning Policy Framework (February 2019), which can be viewed at:  
<https://www.gov.uk/government/publications/national-planning-policy-framework--2>