

Surface Water and Foul Water Drainage Strategy

SeAH Monopile Facility, Teesport



L05858-CLK-ZZ-EX.ZZ-TN-C-0001

SeAH Wind Ltd.

| Report No. | Date. |
|-----------------------------|----------|
| SeAH-CLK-ZZ-EX.ZZ-TN-C-0001 | 12/04/22 |

| Project |
|------------------------|
| SeAH Monopile Facility |

| Client Name |
|----------------|
| SeAH Wind Ltd. |

| Issue Date/ Number | Status | Description of Amendments |
|--------------------|--------|---------------------------|
| 12/04/2022 | S2 | First Issue |
| | | |
| | | |
| | | |

| Report Prepared by: | |
|---|--|
| Justin Horsley Civil Engineer |  |
| | |
| | |

| Approved for Issue by: | |
|--|--|
| Samuel Ihle Associate Director |  |

| Issuing Office | |
|----------------|--|
| | The Cocoa House, 129 Cumberland Road, Bristol, BS1 6UY Tel: +44 (0)117 929 2244 |
| | GF Suite, Bickleigh House, Park Five Business Centre, Exeter, EX2 7HU Tel: +44 (0)1392 369098 |
| X | 7 Hatchers Mews, Bermondsey, London SE1 3GS Tel: +44(0)20 7939 0959 |

This report is provided for the benefit of the Client. We do not accept responsibility in the event that the report contents are used in whole or in part by a third party and we exercise no duty of care to any such third party.
© Clarkebond (UK) Limited

Contents

Contents i

1 Introduction 1

2 Planning Condition..... 1

3 Surface Water Drainage 2

4 Foul Water Drainage 3

5 Operation and Maintenance 3

6 Conclusion 4

7 APPENDICES 5

Figure 1 - Surface Water Networks 2

Figure 2 - Foul Water Networks 3

Figure 3 - SWS Summary 4

1 Introduction

- 1.1.1 SeAH Wind Ltd. will develop a Monopile Manufacturing Facility in Teesport, North Yorkshire, United Kingdom.
- 1.1.2 This report has been produced by Clarkebond (UK) Limited on behalf of SeAH Wind Ltd. to set out the strategy for disposal of Surface Water and Foul Water from the proposed development so as not to cause flooding to the site or third party land.

2 Planning Condition

The planning conditions related to drainage is outline Condition 13. For clarity the wording of the condition is as follows:

Prior to the commencement of the development, or in accordance with the phasing plan agreed through discharge of condition 4, a detailed scheme for the disposal of foul and surface water from the development hereby approved shall be submitted to and approved in writing by the Local Planning Authority in consultation with Northumbrian Water and the Lead Local Flood Authority. Thereafter the development shall take place in accordance with the approved details.

This report provides the details required to clear this condition.

3 Surface Water Drainage

The surface water drainage is divided into 4 separate networks which are indicated in Figure 1 below.




Figure 1 - Surface Water Networks

Network 1 will be draining approximately 4.2ha (hectares) of clean surface water runoff from the roofs of the Monopile Facility, Power Station 2, Workers Room, Maintenance Station and Welding Consumables. It will discharge into an existing manhole within the curtilage of the site, fitted with a non-return valve and discharges freely into the South Bank Arterial Drainage Channel as seen in Appendix C.

Network 2 will be draining approximately 5.5ha of surface water runoff from the concrete service yard, tarmac car parking areas and Main Office building. The runoff will pass through a petrol interceptor before discharging into an existing manhole within the curtilage of the site, fitted with a non-return valve and discharges freely into the South Bank Arterial Drainage Channel.

Network 3 will be draining approximately 7.7ha of surface water runoff from the Monopile Facility, Power Station 1 and tarmac areas surrounding the building where HGV's will be tracking. The network is separated so that the clean surface water discharge from the buildings will connect downstream of a petrol interceptor and the runoff for the tarmac areas will pass through the petrol interceptor before connecting into an existing manhole within the curtilage of the site, fitted with a non-return valve and discharging freely into the South Bank Arterial Drainage Channel.

Network 4 will be draining approximately 2.5ha of surface water runoff from the tarmac car parking area. The runoff will pass through a petrol interceptor before discharging into an existing manhole within the curtilage of the site, fitted with a non-return valve and discharging freely into the South Bank Arterial Drainage Channel.

4 Foul Water Drainage

The foul water drainage is separated into two separate networks which are indicated in Figure 2 below.




Figure 2 - Foul Water Networks

Network 1 will be taking half of the development via gravity to a package pump station chamber at the boundary of the development which will then pump water into the existing system within the access road. There will be a grease trap outside the Workers Room prevent grease and fats from the kitchen entering the foul network and blocking the pipework. The gatehouse located at the northern side of the development near the quay will require a small package pump station and pumped main that will discharge into a manhole within the development, then discharging via gravity to the aforementioned package pump station at the boundary of the development. A chemical dosing unit will be installed where required.

Network 2 will be taking the other half of the development via gravity to a proposed manhole on the boundary of the development which will then discharge into the existing system within the access road via gravity. A chemical dosing unit will be installed where required.

5 Operation and Maintenance

The system will remain entirely private and will be owned and maintained by the Management Company appointed by SeAH Wind Ltd. The Operation and Maintenance manual document reference is SEAH-CLK-ZZ-EX.ZZ-RP-C-0001(Drainage Operation and Maintenance Manual).

6 Conclusion

Figure 3 below summarises the key features of the Surface Water systems, which will discharge freely into the South Bank Arterial Drainage Channel.

| Surface Water System Summary | | | | |
|------------------------------|----------|-------------------|------------------------|----------------------|
| Network | Area(ha) | Largest Pipe Dia. | Peak Outfall Discharge | Notes |
| 1 | 4.2 | 750mm | 1304l/s | |
| 2 | 5.5 | 900mm | 1575l/s | Requires Interceptor |
| 3 | 7.7 | 900mm | 2555l/s | Requires Interceptor |
| 4 | 2.5 | 600mm | 915l/s | Requires Interceptor |

Figure 3 - SWS Summary

The foul water system pipe sizing and requirements are subject to detailed design following confirmation of the number of heads at any one time on site, there may also be future requirements of items such as chemical dosing units.


7 APPENDICES

Appendix A – Proposed Drainage Strategy

Appendix B – MicroDrainage Calculations

Appendix C – South Bank Arterial Drainage

Appendix A – Proposed Drainage Strategy




01/03/22 15:06:38
 P:\0151\01515858 - Transport Services - Transport Services - 2021\Templates\EB_A01_Project_Template.rvt
 01/03/22 15:06:38

KEY

- PROPOSED SURFACE WATER DRAINAGE
- PROPOSED FOUL WATER DRAINAGE
- PROPOSED FOUL RISING MAIN
- BUILDING PERIMETER LAND DRAIN
- ALTHON HD1000 (C250, D400, F900 - SEE PLAN)
- SURFACE WATER SYSTEM (BY OTHERS)
- FOUL WATER SYSTEM (BY OTHERS)
- |— PETROL INTERCEPTOR
- |— GREASE TRAP

NOTE: PIPE DIAMETERS AND GRADIENTS TO BE CONFIRMED SUBJECT TO DETAILED DESIGN.



CDM RESIDUAL RISKS

The work shown on this drawing is both familiar to the designers and routinely safely built in similar circumstances by competent contractors. Risks are considered significant.

Signed: S.I.H.E. Date: 11/04/2022

RELEASE OF ELECTRONIC FILES FOR DEVELOPMENT BY OTHERS.

CLARKEBOND RELEASES THIS FILE, WHICH WAS USED TO PRODUCE STRUCTURAL & CIVIL ENGINEERING LAYOUTS & DETAILS, ON THE FOLLOWING CONDITIONS:

- FUTURE USERS OF THIS FILE ARE RESPONSIBLE FOR THE ACCURACY & SUITABILITY OF THE ORIGINAL INFORMATION IN THE FILE FOR THE NEW APPLICATION.
- CLARKEBOND WILL NOT RELEASE OR ADVISE OF CHANGES THAT MAY MAKE TO THEIR ELECTRONIC FILES OTHER THAN THAT REQUIRED FOR THE ISSUE OF THEIR STRUCTURAL & CIVIL ENGINEERING DRAWINGS FOR THE PROJECT.

CLARKEBOND WILL NOT BE RESPONSIBLE FOR:

- ANY INFORMATION PRODUCED BY A THIRD PARTY.
- THE ACCURACY OF THE MODEL FILE ONCE MODIFIED BY OTHERS.

NOTES:

1. DO NOT SCALE FROM THIS DRAWING.
2. CONTRACTOR TO CHECK ALL DIMENSIONS AND REPORT ANY ERRORS AND OMISSIONS TO THE ENGINEER.
3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE ARCHITECT'S DRAWINGS AND THE SPECIFICATIONS.
4. THE CONTRACTOR IS TO BE RESPONSIBLE FOR ALL DIMENSIONS, LEVELS AND FOR THE CORRECT SETTING OUT OF ALL WORKS ON SITE.
5. ALL WORKS ARE TO COMPLY WITH THE RELEVANT STANDARDS AND CODES OF PRACTICE AND TO THE APPROVAL OF THE LOCAL AUTHORITY FOR BUILDING REGULATIONS.
6. INTERNAL DRAIN RULES AND CONNECTION POINTS TO BE CONFIRMED AT DETAILED DESIGN.

| Rev. | Description | By | CHK | Date |
|------|----------------------------|--------|------|----------|
| P01 | 300 PPE DIMENSIONS UPDATED | J.L.H. | S.I. | 11.04.22 |
| P01 | PLANNING | J.L.H. | S.I. | 08.04.22 |

clarkebond

7 Hatchers Mews
Barnsbury
London
SE1 9GS

tel: +44 (0) 20 7939 0959
e-mail: london@clarkebond.com
web: www.clarkebond.com

BRISTOL EXETER LONDON

Client: **SeAH**

Project: **SeAH MONOPILE FACILITY**

Drawing Title: **DRAINAGE STRATEGY LAYOUT**

Drawing Status: **SUITABLE FOR INFORMATION S2**

Drawing No: **SEAH-CLK-ZZ-EX-ZZ-DR-C-1500**

Client Ref No: **LO5858**


Scale: **1/1000**

Sheet No: **002**

Issue Date: **08/04/22**

© This drawing may not be copied without prior written permission.

Appendix B – MicroDrainage Calculations

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 0 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX-ZZ.CA-C-0001 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX-ZZ.CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Surface Network 1

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

| | | | |
|--------------------------------------|--------|---------------------------------------|-------|
| Return Period (years) | 100 | PIMP (%) | 100 |
| M5-60 (mm) | 17.900 | Add Flow / Climate Change (%) | 0 |
| Ratio R | 0.350 | Minimum Backdrop Height (m) | 0.200 |
| Maximum Rainfall (mm/hr) | 50 | Maximum Backdrop Height (m) | 1.500 |
| Maximum Time of Concentration (mins) | 30 | Min Design Depth for Optimisation (m) | 1.200 |
| Foul Sewage (l/s/ha) | 0.000 | Min Vel for Auto Design only (m/s) | 1.00 |
| Volumetric Runoff Coeff. | 0.750 | Min Slope for Optimisation (1:X) | 500 |

Designed with Level Soffits







Time Area Diagram for Surface Network 1

| Time (mins) | Area (ha) | Time (mins) | Area (ha) |
|-------------|-----------|-------------|-----------|
| 0-4 | 1.572 | 4-8 | 2.585 |

Total Area Contributing (ha) = 4.157


Total Pipe Volume (m³) = 191.918

Network Design Table for Surface Network 1






| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Section Type | Auto Design |
|-------|------------|----------|-------------|-------------|-------------|-----------------|--------|----------|----------|--------------|---|
| 1.000 | 52.000 | 0.173 | 300.0 | 0.000 | 5.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 1.001 | 50.000 | 0.167 | 300.0 | 1.576 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 1.002 | 80.000 | 0.267 | 300.0 | 1.363 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 1.003 | 70.000 | 0.233 | 300.0 | 0.075 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 1.004 | 58.605 | 0.219 | 267.4 | 0.066 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 2.000 | 58.300 | 0.259 | 225.0 | 0.803 | 5.00 | 0.0 | 0.600 | o | 450 | Pipe/Conduit |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL E (m) | I.Area (ha) | E Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|--------------|-------------|-------------|-------------|-------------------|------------|----------------|-----------|-----------|------------|
| 1.000 | 50.00 | 5.54 | 7.978 | 0.000 | 0.0 | 0.0 | 0.0 | 1.61 | 711.5 | 0.0 |
| 1.001 | 50.00 | 6.06 | 7.804 | 1.576 | 0.0 | 0.0 | 0.0 | 1.61 | 711.5 | 213.5 |
| 1.002 | 50.00 | 6.88 | 7.638 | 2.939 | 0.0 | 0.0 | 0.0 | 1.61 | 711.5 | 398.0 |
| 1.003 | 50.00 | 7.61 | 7.371 | 3.014 | 0.0 | 0.0 | 0.0 | 1.61 | 711.5 | 408.1 |
| 1.004 | 50.00 | 8.18 | 7.138 | 3.080 | 0.0 | 0.0 | 0.0 | 1.71 | 754.0 | 417.0 |
| 2.000 | 50.00 | 5.72 | 8.125 | 0.803 | 0.0 | 0.0 | 0.0 | 1.35 | 214.9 | 108.8 |


| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 1 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX-ZZ.CA-C-0001 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX-ZZ.CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

Network Design Table for Surface Network 1

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Section Type | Auto Design |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|--------------|---|
| 2.001 | 26.175 | 0.116 | 225.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 450 | Pipe/Conduit |  |
| 2.002 | 11.792 | 0.052 | 225.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 450 | Pipe/Conduit |  |
| 2.003 | 90.000 | 0.400 | 225.0 | 0.191 | 0.00 | 0.0 | 0.600 | o | 450 | Pipe/Conduit |  |
| 2.004 | 17.677 | 0.079 | 225.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 450 | Pipe/Conduit |  |
| 1.005 | 50.390 | 1.819 | 27.7 | 0.083 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|-----------------|----------------|--------------|------------------|----------------------|---------------|-------------------|--------------|--------------|---------------|
| 2.001 | 50.00 | 6.04 | 7.866 | 0.803 | 0.0 | 0.0 | 0.0 | 1.35 | 214.9 | 108.8 |
| 2.002 | 50.00 | 6.19 | 7.750 | 0.803 | 0.0 | 0.0 | 0.0 | 1.35 | 214.9 | 108.8 |
| 2.003 | 50.00 | 7.30 | 7.697 | 0.995 | 0.0 | 0.0 | 0.0 | 1.35 | 214.9 | 134.7 |
| 2.004 | 50.00 | 7.52 | 7.297 | 0.995 | 0.0 | 0.0 | 0.0 | 1.35 | 214.9 | 134.7 |
| 1.005 | 50.00 | 8.34 | 6.919 | 4.157 | 0.0 | 0.0 | 0.0 | 5.33 | 2354.1 | 562.9 |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 2 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX-ZZ.CA-C-0001 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX-ZZ.CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

Area Summary for Surface Network 1


| Pipe Number | PIMP Type | PIMP Name | PIMP (%) | Gross Area (ha) | Imp. Area (ha) | Pipe Total (ha) |
|-------------|-----------|-----------|----------|-----------------|----------------|-----------------|
| 1.000 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 1.001 | User | - | 100 | 1.576 | 1.576 | 1.576 |
| 1.002 | User | - | 100 | 1.363 | 1.363 | 1.363 |
| 1.003 | User | - | 100 | 0.075 | 0.075 | 0.075 |
| 1.004 | User | - | 100 | 0.066 | 0.066 | 0.066 |
| 2.000 | User | - | 100 | 0.803 | 0.803 | 0.803 |
| 2.001 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 2.002 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 2.003 | User | - | 100 | 0.191 | 0.191 | 0.191 |
| 2.004 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 1.005 | User | - | 100 | 0.083 | 0.083 | 0.083 |
| | | | | Total | Total | Total |
| | | | | 4.157 | 4.157 | 4.157 |

Simulation Criteria for Surface Network 1

| | | | |
|---------------------------------|-------|--|-------|
| Volumetric Runoff Coeff | 0.750 | Additional Flow - % of Total Flow | 0.000 |
| Areal Reduction Factor | 1.000 | MADD Factor * 10m ³ /ha Storage | 2.000 |
| Hot Start (mins) | 0 | Inlet Coefficient | 0.800 |
| Hot Start Level (mm) | 0 | Flow per Person per Day (l/per/day) | 0.000 |
| Manhole Headloss Coeff (Global) | 0.500 | Run Time (mins) | 60 |
| Foul Sewage per hectare (l/s) | 0.000 | Output Interval (mins) | 1 |
| Number of Input Hydrographs | 0 | Number of Storage Structures | 0 |
| Number of Online Controls | 0 | Number of Time/Area Diagrams | 0 |
| Number of Offline Controls | 0 | Number of Real Time Controls | 0 |

Synthetic Rainfall Details

| | | | |
|-----------------------|-------------------|-----------------------|--------|
| Rainfall Model | FSR | Profile Type | Summer |
| Return Period (years) | 100 | Cv (Summer) | 0.750 |
| Region | England and Wales | Cv (Winter) | 0.840 |
| M5-60 (mm) | 17.900 | Storm Duration (mins) | 30 |
| Ratio R | 0.350 | | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 3 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX-ZZ.CA-C-0001 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX-ZZ.CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 1

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 0
Number of Online Controls 0 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 17.900 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
720, 960, 1440
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 30


| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surchage | First (Y) Flood | First (Z) Overflow | Overflow Act. |
|-------|------------|-----------|---------------|----------------|--------------------|-----------------|--------------------|---------------|
| 1.000 | S1 | 15 Winter | 1 | +0% | 100/15 Summer | | | |
| 1.001 | S2 | 15 Winter | 1 | +0% | 100/15 Summer | | | |
| 1.002 | S3 | 15 Winter | 1 | +0% | 100/15 Summer | | | |
| 1.003 | S4 | 15 Winter | 1 | +0% | 100/15 Summer | | | |
| 1.004 | S5 | 15 Winter | 1 | +0% | 100/15 Summer | | | |
| 2.000 | S8 | 15 Winter | 1 | +0% | 30/15 Summer | 100/15 Summer | | |
| 2.001 | S9 | 15 Winter | 1 | +0% | 30/15 Summer | | | |
| 2.002 | S10 | 15 Winter | 1 | +0% | 30/15 Summer | | | |
| 2.003 | S11 | 15 Winter | 1 | +0% | 30/15 Summer | | | |
| 2.004 | S12 | 15 Winter | 1 | +0% | 30/15 Summer | | | |
| 1.005 | S6 | 15 Winter | 1 | +0% | | | | |

| PN | US/MH Name | Water Surcharged Flooded | | | Half Drain Pipe | | Pipe Flow (l/s) | Level Exceeded |
|-------|------------|--------------------------|-----------|--------------------------|-------------------|-------------|-----------------|----------------|
| | | Level (m) | Depth (m) | Volume (m ³) | Flow / Cap. (l/s) | Time (mins) | | |
| 1.000 | S1 | 8.081 | -0.647 | 0.000 | 0.00 | | 1.1 | OK |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 4 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX-ZZ.CA-C-0001 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX-ZZ.CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 1

| PN | US/MH Name | Water | | Surcharged | | Flooded | | Half Drain Pipe | | Status | Level Exceeded |
|-------|---------------|--------------|--------------|-----------------------------|----------------|-------------------|----------------|-----------------|----|--------|-------------------|
| | | Level (m) | Depth (m) | Volume (m ³) | Flow / Cap. | Overflow (l/s) | Time (mins) | Flow (l/s) | | | |
| 1.001 | S2 | 8.081 | -0.474 | 0.000 | 0.24 | | | 142.1 | OK | | |
| 1.002 | S3 | 7.974 | -0.414 | 0.000 | 0.41 | | | 260.1 | OK | | |
| 1.003 | S4 | 7.709 | -0.412 | 0.000 | 0.41 | | | 259.0 | OK | | |
| 1.004 | S5 | 7.467 | -0.421 | 0.000 | 0.40 | | | 258.1 | OK | | |
| 2.000 | S8 | 8.347 | -0.228 | 0.000 | 0.47 | | | 92.5 | OK | | 2 |
| 2.001 | S9 | 8.092 | -0.223 | 0.000 | 0.50 | | | 90.9 | OK | | |
| 2.002 | S10 | 7.996 | -0.203 | 0.000 | 0.58 | | | 90.1 | OK | | |
| 2.003 | S11 | 7.930 | -0.217 | 0.000 | 0.50 | | | 102.0 | OK | | |
| 2.004 | S12 | 7.549 | -0.198 | 0.000 | 0.60 | | | 101.6 | OK | | |
| 1.005 | S6 | 7.130 | -0.539 | 0.000 | 0.18 | | | 349.4 | OK | | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 5 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX-ZZ.CA-C-0001 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX-ZZ.CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 1

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 0
Number of Online Controls 0 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 17.900 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
720, 960, 1440
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 30

| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surchage | First (Y) Flood | First (Z) Overflow | Overflow Act. |
|-------|------------|-----------|---------------|----------------|--------------------|-----------------|--------------------|---------------|
| 1.000 | S1 | 15 Winter | 30 | +0% | 100/15 Summer | | | |
| 1.001 | S2 | 15 Winter | 30 | +0% | 100/15 Summer | | | |
| 1.002 | S3 | 15 Winter | 30 | +0% | 100/15 Summer | | | |
| 1.003 | S4 | 15 Winter | 30 | +0% | 100/15 Summer | | | |
| 1.004 | S5 | 15 Winter | 30 | +0% | 100/15 Summer | | | |
| 2.000 | S8 | 15 Winter | 30 | +0% | 30/15 Summer | 100/15 Summer | | |
| 2.001 | S9 | 15 Winter | 30 | +0% | 30/15 Summer | | | |
| 2.002 | S10 | 15 Winter | 30 | +0% | 30/15 Summer | | | |
| 2.003 | S11 | 15 Winter | 30 | +0% | 30/15 Summer | | | |
| 2.004 | S12 | 15 Winter | 30 | +0% | 30/15 Summer | | | |
| 1.005 | S6 | 15 Winter | 30 | +0% | | | | |


| PN | US/MH Name | Water Level (m) | Surcharged Depth (m) | Flooded Volume (m ³) | Flow / Overflow Cap. (l/s) | Half Drain Time (mins) | Pipe Flow (l/s) | Status |
|-------|------------|-----------------|----------------------|----------------------------------|----------------------------|------------------------|-----------------|--------|
| | | | | | | | | |
| 1.000 | S1 | 8.365 | -0.363 | 0.000 | 0.00 | | 2.5 | OK |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 6 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX-ZZ.CA-C-0001 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX-ZZ.CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 1

| PN | US/MH Name | Water Level (m) | Surcharged Depth (m) | Flooded Volume (m³) | Flow / Overflow Cap. (l/s) | Half Drain Time (mins) | Pipe Flow (l/s) | Status |
|-------|------------|-----------------|----------------------|---------------------|----------------------------|------------------------|-----------------|------------|
| | | | | | | | | |
| 1.001 | S2 | 8.365 | -0.190 | 0.000 | 0.57 | | 344.4 | OK |
| 1.002 | S3 | 8.286 | -0.102 | 0.000 | 0.99 | | 631.9 | OK |
| 1.003 | S4 | 7.986 | -0.135 | 0.000 | 1.00 | | 624.3 | OK |
| 1.004 | S5 | 7.721 | -0.166 | 0.000 | 0.96 | | 622.7 | OK |
| 2.000 | S8 | 8.681 | 0.106 | 0.000 | 1.10 | | 217.9 | SURCHARGED |
| 2.001 | S9 | 8.462 | 0.146 | 0.000 | 1.05 | | 190.6 | SURCHARGED |
| 2.002 | S10 | 8.344 | 0.144 | 0.000 | 1.22 | | 189.9 | SURCHARGED |
| 2.003 | S11 | 8.234 | 0.087 | 0.000 | 1.04 | | 212.0 | SURCHARGED |
| 2.004 | S12 | 7.789 | 0.041 | 0.000 | 1.24 | | 209.9 | SURCHARGED |
| 1.005 | S6 | 7.256 | -0.412 | 0.000 | 0.42 | | 830.4 | OK |

| PN | US/MH Name | Level Exceeded |
|-------|------------|----------------|
| 1.000 | S1 | |
| 1.001 | S2 | |
| 1.002 | S3 | |
| 1.003 | S4 | |
| 1.004 | S5 | |
| 2.000 | S8 | 2 |
| 2.001 | S9 | |
| 2.002 | S10 | |
| 2.003 | S11 | |
| 2.004 | S12 | |
| 1.005 | S6 | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 7 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX-ZZ.CA-C-0001 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX-ZZ.CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 0
Number of Online Controls 0 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 17.900 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
720, 960, 1440
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 30

| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surchage | First (Y) Flood | First (Z) Overflow | Overflow Act. |
|-------|------------|-----------|---------------|----------------|--------------------|-----------------|--------------------|---------------|
| 1.000 | S1 | 15 Winter | 100 | +30% | 100/15 Summer | | | |
| 1.001 | S2 | 15 Winter | 100 | +30% | 100/15 Summer | | | |
| 1.002 | S3 | 15 Winter | 100 | +30% | 100/15 Summer | | | |
| 1.003 | S4 | 15 Winter | 100 | +30% | 100/15 Summer | | | |
| 1.004 | S5 | 15 Winter | 100 | +30% | 100/15 Summer | | | |
| 2.000 | S8 | 15 Winter | 100 | +30% | 30/15 Summer | 100/15 Summer | | |
| 2.001 | S9 | 15 Winter | 100 | +30% | 30/15 Summer | | | |
| 2.002 | S10 | 15 Winter | 100 | +30% | 30/15 Summer | | | |
| 2.003 | S11 | 15 Winter | 100 | +30% | 30/15 Summer | | | |
| 2.004 | S12 | 15 Winter | 100 | +30% | 30/15 Summer | | | |
| 1.005 | S6 | 15 Winter | 100 | +30% | | | | |


| PN | US/MH Name | Water | | | Surcharged | | Flooded | | Half Drain Time (mins) | Pipe Flow (l/s) | Status |
|-------|------------|-----------|-----------|--------------------------|-------------|--------------|---------|--|------------------------|-----------------|--------|
| | | Level (m) | Depth (m) | Volume (m ³) | Flow / Cap. | Flow / (l/s) | | | | | |
| 1.000 | S1 | 9.446 | 0.718 | 0.000 | 0.02 | | | | 9.6 | SURCHARGED | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 8 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX-ZZ.CA-C-0001 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX-ZZ.CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 1

| PN | US/MH Name | Water | Surcharged | Flooded | Half Drain | | Pipe | Status |
|-------|------------|-----------|------------|-------------|-----------------------|-------------|------------|------------|
| | | Level (m) | Depth (m) | Volume (m³) | Flow / Overflow (l/s) | Time (mins) | Flow (l/s) | |
| 1.001 | S2 | 9.450 | 0.895 | 0.000 | 0.89 | | 532.3 | SURCHARGED |
| 1.002 | S3 | 9.339 | 0.951 | 0.000 | 1.54 | | 978.8 | SURCHARGED |
| 1.003 | S4 | 8.711 | 0.590 | 0.000 | 1.55 | | 971.7 | SURCHARGED |
| 1.004 | S5 | 8.137 | 0.250 | 0.000 | 1.49 | | 969.5 | SURCHARGED |
| 2.000 | S8 | 10.007 | 1.432 | 6.767 | 1.43 | | 283.3 | FLOOD |
| 2.001 | S9 | 9.566 | 1.250 | 0.000 | 1.54 | | 279.5 | SURCHARGED |
| 2.002 | S10 | 9.296 | 1.097 | 0.000 | 1.79 | | 279.1 | SURCHARGED |
| 2.003 | S11 | 9.062 | 0.915 | 0.000 | 1.60 | | 324.9 | SURCHARGED |
| 2.004 | S12 | 7.981 | 0.234 | 0.000 | 1.92 | | 324.5 | SURCHARGED |
| 1.005 | S6 | 7.364 | -0.305 | 0.000 | 0.66 | | 1303.7 | OK |

| PN | US/MH Name | Level Exceeded |
|-------|------------|----------------|
| 1.000 | S1 | |
| 1.001 | S2 | |
| 1.002 | S3 | |
| 1.003 | S4 | |
| 1.004 | S5 | |
| 2.000 | S8 | 2 |
| 2.001 | S9 | |
| 2.002 | S10 | |
| 2.003 | S11 | |
| 2.004 | S12 | |
| 1.005 | S6 | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 0 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0002 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-M3-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Surface Network 2

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

| | | | |
|--------------------------------------|--------|---------------------------------------|-------|
| Return Period (years) | 100 | PIMP (%) | 100 |
| M5-60 (mm) | 17.900 | Add Flow / Climate Change (%) | 0 |
| Ratio R | 0.350 | Minimum Backdrop Height (m) | 0.200 |
| Maximum Rainfall (mm/hr) | 50 | Maximum Backdrop Height (m) | 1.500 |
| Maximum Time of Concentration (mins) | 30 | Min Design Depth for Optimisation (m) | 1.200 |
| Foul Sewage (l/s/ha) | 0.000 | Min Vel for Auto Design only (m/s) | 1.00 |
| Volumetric Runoff Coeff. | 0.750 | Min Slope for Optimisation (1:X) | 500 |

Designed with Level Soffits






Time Area Diagram for Surface Network 2

| Time (mins) | Area (ha) | Time (mins) | Area (ha) | Time (mins) | Area (ha) |
|-------------|-----------|-------------|-----------|-------------|-----------|
| 0-4 | 1.907 | 4-8 | 3.141 | 8-12 | 0.407 |

Total Area Contributing (ha) = 5.455


Total Pipe Volume (m³) = 205.974

Network Design Table for Surface Network 2









| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Section | Type | Auto Design |
|-------|------------|----------|-------------|-------------|-------------|-----------------|--------|----------|----------|--------------|------|---|
| 1.000 | 70.000 | 0.233 | 300.0 | 1.233 | 5.00 | 0.0 | 0.600 | o | 600 | Pipe/Conduit | |  |
| 1.001 | 70.000 | 0.233 | 300.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 600 | Pipe/Conduit | |  |
| 2.000 | 60.000 | 0.512 | 117.1 | 0.821 | 5.00 | 0.0 | 0.600 | o | 450 | Pipe/Conduit | |  |
| 1.002 | 38.682 | 0.129 | 300.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit | |  |
| 1.003 | 70.000 | 0.156 | 450.0 | 1.930 | 0.00 | 0.0 | 0.600 | o | 900 | Pipe/Conduit | |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|--------------|-------------|-----------|---------------|-------------------|------------|----------------|-----------|-----------|------------|
| 1.000 | 50.00 | 5.83 | 6.914 | 1.233 | 0.0 | 0.0 | 0.0 | 1.40 | 396.0 | 166.9 |
| 1.001 | 50.00 | 6.67 | 6.681 | 1.233 | 0.0 | 0.0 | 0.0 | 1.40 | 396.0 | 166.9 |
| 2.000 | 50.00 | 5.53 | 6.954 | 0.821 | 0.0 | 0.0 | 0.0 | 1.88 | 298.6 | 111.2 |
| 1.002 | 50.00 | 7.07 | 6.099 | 2.054 | 0.0 | 0.0 | 0.0 | 1.61 | 711.5 | 278.2 |
| 1.003 | 50.00 | 7.86 | 5.716 | 3.984 | 0.0 | 0.0 | 0.0 | 1.47 | 935.5 | 539.4 |


| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 1 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0002 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-M3-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

Network Design Table for Surface Network 2

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Section Type | Auto Design |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|--------------|---|
| 1.004 | 41.002 | 0.091 | 450.0 | 0.145 | 0.00 | 0.0 | 0.600 | o | 900 | Pipe/Conduit |  |
| 1.005 | 58.370 | 0.130 | 450.0 | 0.710 | 0.00 | 0.0 | 0.600 | o | 900 | Pipe/Conduit |  |
| 3.000 | 30.000 | 0.805 | 37.3 | 0.418 | 5.00 | 0.0 | 0.600 | o | 300 | Pipe/Conduit |  |
| 1.006 | 16.000 | 0.036 | 450.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 900 | Pipe/Conduit |  |
| 1.007 | 12.105 | 0.027 | 450.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 900 | Pipe/Conduit |  |
| 4.000 | 60.000 | 0.794 | 75.6 | 0.091 | 5.00 | 0.0 | 0.600 | o | 225 | Pipe/Conduit |  |
| 4.001 | 46.130 | 0.383 | 120.4 | 0.107 | 0.00 | 0.0 | 0.600 | o | 225 | Pipe/Conduit |  |
| 1.008 | 12.242 | 0.027 | 453.4 | 0.000 | 0.00 | 0.0 | 0.600 | o | 900 | Pipe/Conduit |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|-----------------|----------------|--------------|------------------|----------------------|---------------|-------------------|--------------|--------------|---------------|
| 1.004 | 50.00 | 8.32 | 5.560 | 4.129 | 0.0 | 0.0 | 0.0 | 1.47 | 935.5 | 559.1 |
| 1.005 | 50.00 | 8.99 | 5.469 | 4.839 | 0.0 | 0.0 | 0.0 | 1.47 | 935.5 | 655.3 |
| 3.000 | 50.00 | 5.19 | 7.805 | 0.418 | 0.0 | 0.0 | 0.0 | 2.58 | 182.7 | 56.7 |
| 1.006 | 50.00 | 9.17 | 5.340 | 5.258 | 0.0 | 0.0 | 0.0 | 1.47 | 935.5 | 712.0 |
| 1.007 | 50.00 | 9.30 | 5.304 | 5.258 | 0.0 | 0.0 | 0.0 | 1.47 | 935.5 | 712.0 |
| 4.000 | 50.00 | 5.66 | 8.294 | 0.091 | 0.0 | 0.0 | 0.0 | 1.51 | 59.9 | 12.3 |
| 4.001 | 50.00 | 6.31 | 7.500 | 0.198 | 0.0 | 0.0 | 0.0 | 1.19 | 47.3 | 26.8 |
| 1.008 | 50.00 | 9.44 | 5.277 | 5.455 | 0.0 | 0.0 | 0.0 | 1.46 | 931.9 | 738.7 |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 2 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0002 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-M3-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

Area Summary for Surface Network 2

| Pipe Number | PIMP Type | PIMP Name | PIMP (%) | Gross Area (ha) | Imp. Area (ha) | Pipe Total (ha) |
|-------------|-----------|-----------|----------|-----------------|----------------|-----------------|
| 1.000 | User | - | 100 | 1.233 | 1.233 | 1.233 |
| 1.001 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 2.000 | User | - | 100 | 0.821 | 0.821 | 0.821 |
| 1.002 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 1.003 | User | - | 100 | 0.168 | 0.168 | 0.168 |
| | User | - | 100 | 0.138 | 0.138 | 0.307 |
| | User | - | 100 | 1.623 | 1.623 | 1.930 |
| 1.004 | User | - | 100 | 0.145 | 0.145 | 0.145 |
| 1.005 | User | - | 100 | 0.353 | 0.353 | 0.353 |
| | User | - | 100 | 0.357 | 0.357 | 0.710 |
| 3.000 | User | - | 100 | 0.194 | 0.194 | 0.194 |
| | User | - | 100 | 0.225 | 0.225 | 0.418 |
| 1.006 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 1.007 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 4.000 | User | - | 100 | 0.091 | 0.091 | 0.091 |
| 4.001 | User | - | 100 | 0.107 | 0.107 | 0.107 |
| 1.008 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| | | | | Total | Total | Total |
| | | | | 5.455 | 5.455 | 5.455 |

Free Flowing Outfall Details for Surface Network 2

| Outfall Pipe Number | Outfall Name | C. Level (m) | I. Level (m) | Min I. Level (m) | D, L (mm) | W (mm) |
|---------------------|--------------|--------------|--------------|------------------|-----------|--------|
|---------------------|--------------|--------------|--------------|------------------|-----------|--------|

| | | | | | | |
|-------|-----|-------|-------|-------|------|---|
| 1.008 | S22 | 9.657 | 5.250 | 0.000 | 1800 | 0 |
|-------|-----|-------|-------|-------|------|---|


Simulation Criteria for Surface Network 2

| | | | |
|---------------------------------|-------|-------------------------------------|-------|
| Volumetric Runoff Coeff | 0.750 | Additional Flow - % of Total Flow | 0.000 |
| Areal Reduction Factor | 1.000 | MADD Factor * 10m³/ha Storage | 2.000 |
| Hot Start (mins) | 0 | Inlet Coefficient | 0.800 |
| Hot Start Level (mm) | 0 | Flow per Person per Day (l/per/day) | 0.000 |
| Manhole Headloss Coeff (Global) | 0.500 | Run Time (mins) | 60 |
| Foul Sewage per hectare (l/s) | 0.000 | Output Interval (mins) | 1 |

| | | | |
|-----------------------------|---|------------------------------|---|
| Number of Input Hydrographs | 0 | Number of Storage Structures | 0 |
| Number of Online Controls | 0 | Number of Time/Area Diagrams | 0 |
| Number of Offline Controls | 0 | Number of Real Time Controls | 0 |

Synthetic Rainfall Details

| | | | |
|-----------------------|-------------------|-----------------------|--------|
| Rainfall Model | FSR | Profile Type | Summer |
| Return Period (years) | 100 | Cv (Summer) | 0.750 |
| Region | England and Wales | Cv (Winter) | 0.840 |
| M5-60 (mm) | 17.900 | Storm Duration (mins) | 30 |
| Ratio R | 0.350 | | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 3 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0002 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-M3-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 2

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 0
Number of Online Controls 0 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0


Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 17.900 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON


Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 30

| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surcharge | First (Y) Flood | First (Z) Overflow | Overflow Act. |
|-------|------------|-----------|---------------|----------------|---------------------|-----------------|--------------------|---------------|
| 1.000 | S13 | 15 Winter | 1 | +0% | 100/15 Summer | 100/15 Summer | | |
| 1.001 | S14 | 15 Winter | 1 | +0% | 100/15 Summer | | | |
| 2.000 | S25 | 15 Winter | 1 | +0% | 100/15 Summer | 100/15 Summer | | |
| 1.002 | S15 | 15 Winter | 1 | +0% | 30/15 Winter | | | |
| 1.003 | S16 | 15 Winter | 1 | +0% | 30/15 Summer | | | |
| 1.004 | S17 | 15 Winter | 1 | +0% | 30/15 Summer | | | |
| 1.005 | S18 | 15 Winter | 1 | +0% | 30/15 Summer | | | |
| 3.000 | S51 | 15 Winter | 1 | +0% | 100/15 Summer | | | |
| 1.006 | S19 | 15 Winter | 1 | +0% | 30/15 Summer | | | |
| 1.007 | S20 | 15 Winter | 1 | +0% | 30/15 Summer | | | |
| 4.000 | S23 | 15 Winter | 1 | +0% | 100/15 Summer | | | |
| 4.001 | S24 | 15 Winter | 1 | +0% | 30/15 Summer | | | |
| 1.008 | S21 | 15 Winter | 1 | +0% | 30/15 Summer | | | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 4 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0002 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-M3-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 2

| PN | US/MH Name | Water | Surcharged | Flooded | Half Drain Pipe | | Status | Level Exceeded |
|-------|---------------|--------------|--------------|-----------------------------|----------------------------------|----------------|--------|-------------------|
| | | Level (m) | Depth (m) | Volume (m ³) | Flow / Overflow Cap. (l/s) | Time (mins) | | |
| 1.000 | S13 | 7.181 | -0.333 | 0.000 | 0.39 | | OK | 4 |
| 1.001 | S14 | 6.938 | -0.343 | 0.000 | 0.38 | | OK | |
| 2.000 | S25 | 7.140 | -0.264 | 0.000 | 0.35 | | OK | 4 |
| 1.002 | S15 | 6.420 | -0.428 | 0.000 | 0.38 | | OK | |
| 1.003 | S16 | 6.219 | -0.397 | 0.000 | 0.47 | | OK | |
| 1.004 | S17 | 6.121 | -0.339 | 0.000 | 0.48 | | OK | |
| 1.005 | S18 | 6.066 | -0.303 | 0.000 | 0.50 | | OK | |
| 3.000 | S51 | 7.918 | -0.187 | 0.000 | 0.30 | | OK | |
| 1.006 | S19 | 5.992 | -0.248 | 0.000 | 0.79 | | OK | |
| 1.007 | S20 | 5.949 | -0.255 | 0.000 | 0.89 | | OK | |
| 4.000 | S23 | 8.360 | -0.159 | 0.000 | 0.18 | | OK | |
| 4.001 | S24 | 7.609 | -0.116 | 0.000 | 0.47 | | OK | |
| 1.008 | S21 | 5.913 | -0.264 | 0.000 | 0.91 | | OK | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 5 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0002 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-M3-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 2

Simulation Criteria

| | | | |
|---------------------------------|-------|--|-------|
| Areal Reduction Factor | 1.000 | Additional Flow - % of Total Flow | 0.000 |
| Hot Start (mins) | 0 | MADD Factor * 10m ³ /ha Storage | 2.000 |
| Hot Start Level (mm) | 0 | Inlet Coefficient | 0.800 |
| Manhole Headloss Coeff (Global) | 0.500 | Flow per Person per Day (l/per/day) | 0.000 |
| Foul Sewage per hectare (l/s) | 0.000 | | |

| | | | |
|-----------------------------|---|------------------------------|---|
| Number of Input Hydrographs | 0 | Number of Storage Structures | 0 |
| Number of Online Controls | 0 | Number of Time/Area Diagrams | 0 |
| Number of Offline Controls | 0 | Number of Real Time Controls | 0 |


Synthetic Rainfall Details

| | | | |
|----------------|-------------------|--------------------|-------|
| Rainfall Model | FSR | Ratio R | 0.350 |
| Region | England and Wales | Cv (Summer) | 0.750 |
| M5-60 (mm) | | 17.900 Cv (Winter) | 0.840 |

| | |
|------------------------------------|---------------------------------|
| Margin for Flood Risk Warning (mm) | 300.0 |
| Analysis Timestep | 2.5 Second Increment (Extended) |
| DTS Status | OFF |
| DVD Status | ON |
| Inertia Status | ON |

| | |
|--------------------------|-------------------|
| Profile(s) | Summer and Winter |
| Duration(s) (mins) | 15, 30, 60 |
| Return Period(s) (years) | 1, 30, 100 |
| Climate Change (%) | 0, 0, 30 |

| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surchage | First (Y) Flood | First (Z) Overflow | Overflow Act. |
|-------|------------|-----------|---------------|----------------|--------------------|-----------------|--------------------|---------------|
| 1.000 | S13 | 15 Winter | 30 | +0% | 100/15 Summer | 100/15 Summer | | |
| 1.001 | S14 | 15 Winter | 30 | +0% | 100/15 Summer | | | |
| 2.000 | S25 | 15 Winter | 30 | +0% | 100/15 Summer | 100/15 Summer | | |
| 1.002 | S15 | 15 Winter | 30 | +0% | 30/15 Winter | | | |
| 1.003 | S16 | 15 Winter | 30 | +0% | 30/15 Summer | | | |
| 1.004 | S17 | 15 Winter | 30 | +0% | 30/15 Summer | | | |
| 1.005 | S18 | 15 Winter | 30 | +0% | 30/15 Summer | | | |
| 3.000 | S51 | 15 Winter | 30 | +0% | 100/15 Summer | | | |
| 1.006 | S19 | 15 Winter | 30 | +0% | 30/15 Summer | | | |
| 1.007 | S20 | 15 Winter | 30 | +0% | 30/15 Summer | | | |
| 4.000 | S23 | 15 Winter | 30 | +0% | 100/15 Summer | | | |
| 4.001 | S24 | 15 Winter | 30 | +0% | 30/15 Summer | | | |
| 1.008 | S21 | 15 Winter | 30 | +0% | 30/15 Summer | | | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 6 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0002 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-M3-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 2

| PN | US/MH Name | Water | Surcharged | Flooded | Half Drain | | Pipe | Status |
|-------|---------------|--------------|--------------|----------------|----------------|-------------------|----------------|------------|
| | | Level (m) | Depth (m) | Volume (m³) | Flow / Cap. | Overflow (l/s) | Time (mins) | |
| 1.000 | S13 | 7.398 | -0.116 | 0.000 | 0.96 | | 343.1 | OK |
| 1.001 | S14 | 7.137 | -0.144 | 0.000 | 0.90 | | 323.3 | OK |
| 2.000 | S25 | 7.281 | -0.123 | 0.000 | 0.85 | | 234.1 | OK |
| 1.002 | S15 | 6.975 | 0.126 | 0.000 | 0.79 | | 457.6 | SURCHARGED |
| 1.003 | S16 | 6.899 | 0.283 | 0.000 | 0.99 | | 792.7 | SURCHARGED |
| 1.004 | S17 | 6.773 | 0.313 | 0.000 | 1.08 | | 794.8 | SURCHARGED |
| 1.005 | S18 | 6.677 | 0.307 | 0.000 | 1.15 | | 900.0 | SURCHARGED |
| 3.000 | S51 | 7.998 | -0.107 | 0.000 | 0.73 | | 121.0 | OK |
| 1.006 | S19 | 6.505 | 0.266 | 0.000 | 1.93 | | 950.1 | SURCHARGED |
| 1.007 | S20 | 6.410 | 0.206 | 0.000 | 2.18 | | 949.1 | SURCHARGED |
| 4.000 | S23 | 8.401 | -0.118 | 0.000 | 0.45 | | 25.8 | OK |
| 4.001 | S24 | 7.870 | 0.145 | 0.000 | 1.18 | | 53.4 | SURCHARGED |
| 1.008 | S21 | 6.294 | 0.117 | 0.000 | 2.26 | | 977.9 | SURCHARGED |

| PN | US/MH Name | Level Exceeded |
|-------|---------------|-------------------|
| 1.000 | S13 | 4 |
| 1.001 | S14 | |
| 2.000 | S25 | 4 |
| 1.002 | S15 | |
| 1.003 | S16 | |
| 1.004 | S17 | |
| 1.005 | S18 | |
| 3.000 | S51 | |
| 1.006 | S19 | |
| 1.007 | S20 | |
| 4.000 | S23 | |
| 4.001 | S24 | |
| 1.008 | S21 | |

129 Cumberland Road
 Bristol
 BS1 6UY

SEAH-CLK-ZZ-EX.ZZ-CA-C-0002



Date 11/04/2022

Designed by Justin Horsley

File SEAH-CLK-ZZ-EX.ZZ-M3-C-...

Checked by Samuel Ihle

XP Solutions

Network 2020.1

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 2

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 0
 Number of Online Controls 0 Number of Time/Area Diagrams 0
 Number of Offline Controls 0 Number of Real Time Controls 0


Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.350
 Region England and Wales Cv (Summer) 0.750
 M5-60 (mm) 17.900 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
 Analysis Timestep 2.5 Second Increment (Extended)
 DTS Status OFF
 DVD Status ON
 Inertia Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60
 Return Period(s) (years) 1, 30, 100
 Climate Change (%) 0, 0, 30


| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surchage | First (Y) Flood | First (Z) Overflow | Overflow Act. |
|-------|------------|-----------|---------------|----------------|--------------------|-----------------|--------------------|---------------|
| 1.000 | S13 | 15 Winter | 100 | +30% | 100/15 Summer | 100/15 Summer | | |
| 1.001 | S14 | 15 Winter | 100 | +30% | 100/15 Summer | | | |
| 2.000 | S25 | 15 Winter | 100 | +30% | 100/15 Summer | 100/15 Summer | | |
| 1.002 | S15 | 15 Winter | 100 | +30% | 30/15 Winter | | | |
| 1.003 | S16 | 15 Winter | 100 | +30% | 30/15 Summer | | | |
| 1.004 | S17 | 15 Winter | 100 | +30% | 30/15 Summer | | | |
| 1.005 | S18 | 15 Winter | 100 | +30% | 30/15 Summer | | | |
| 3.000 | S51 | 15 Winter | 100 | +30% | 100/15 Summer | | | |
| 1.006 | S19 | 15 Winter | 100 | +30% | 30/15 Summer | | | |
| 1.007 | S20 | 15 Winter | 100 | +30% | 30/15 Summer | | | |
| 4.000 | S23 | 15 Winter | 100 | +30% | 100/15 Summer | | | |
| 4.001 | S24 | 15 Winter | 100 | +30% | 30/15 Summer | | | |
| 1.008 | S21 | 15 Winter | 100 | +30% | 30/15 Summer | | | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 8 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0002 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-M3-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 2

| PN | US/MH Name | Water | Surcharged | Flooded | Flow / Overflow Cap. (l/s) | Half Drain | Pipe | Status |
|-------|------------|-----------|------------|-------------|----------------------------|-------------|------------|------------|
| | | Level (m) | Depth (m) | Volume (m³) | | Time (mins) | Flow (l/s) | |
| 1.000 | S13 | 8.741 | 1.227 | 27.731 | 1.34 | | 480.0 | FLOOD |
| 1.001 | S14 | 8.683 | 1.402 | 0.000 | 1.05 | | 376.1 | FLOOD RISK |
| 2.000 | S25 | 8.623 | 1.219 | 19.524 | 1.15 | | 316.7 | FLOOD |
| 1.002 | S15 | 8.552 | 1.703 | 0.000 | 1.02 | | 591.3 | SURCHARGED |
| 1.003 | S16 | 8.469 | 1.853 | 0.000 | 1.46 | | 1168.5 | SURCHARGED |
| 1.004 | S17 | 8.190 | 1.730 | 0.000 | 1.62 | | 1193.7 | SURCHARGED |
| 1.005 | S18 | 7.924 | 1.554 | 0.000 | 1.77 | | 1386.3 | SURCHARGED |
| 3.000 | S51 | 8.395 | 0.290 | 0.000 | 1.16 | | 193.2 | SURCHARGED |
| 1.006 | S19 | 7.498 | 1.258 | 0.000 | 3.05 | | 1498.5 | SURCHARGED |
| 1.007 | S20 | 7.048 | 0.843 | 0.000 | 3.46 | | 1503.4 | SURCHARGED |
| 4.000 | S23 | 8.918 | 0.399 | 0.000 | 0.67 | | 38.8 | SURCHARGED |
| 4.001 | S24 | 8.570 | 0.845 | 0.000 | 1.78 | | 80.5 | SURCHARGED |
| 1.008 | S21 | 6.595 | 0.418 | 0.000 | 3.64 | | 1574.7 | SURCHARGED |

| PN | US/MH Name | Level Exceeded |
|-------|------------|----------------|
| 1.000 | S13 | 4 |
| 1.001 | S14 | |
| 2.000 | S25 | 4 |
| 1.002 | S15 | |
| 1.003 | S16 | |
| 1.004 | S17 | |
| 1.005 | S18 | |
| 3.000 | S51 | |
| 1.006 | S19 | |
| 1.007 | S20 | |
| 4.000 | S23 | |
| 4.001 | S24 | |
| 1.008 | S21 | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 0 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0003 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Surface Network 3

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

| | | | |
|--------------------------------------|--------|---------------------------------------|-------|
| Return Period (years) | 100 | PIMP (%) | 100 |
| M5-60 (mm) | 17.900 | Add Flow / Climate Change (%) | 0 |
| Ratio R | 0.350 | Minimum Backdrop Height (m) | 0.200 |
| Maximum Rainfall (mm/hr) | 50 | Maximum Backdrop Height (m) | 1.500 |
| Maximum Time of Concentration (mins) | 30 | Min Design Depth for Optimisation (m) | 1.200 |
| Foul Sewage (l/s/ha) | 0.000 | Min Vel for Auto Design only (m/s) | 1.00 |
| Volumetric Runoff Coeff. | 0.750 | Min Slope for Optimisation (1:X) | 500 |

Designed with Level Soffits

Time Area Diagram for Surface Network 3





| Time (mins) | Area (ha) | Time (mins) | Area (ha) | Time (mins) | Area (ha) |
|-------------|-----------|-------------|-----------|-------------|-----------|
| 0-4 | 2.414 | 4-8 | 4.834 | 8-12 | 0.432 |

Total Area Contributing (ha) = 7.681

Total Pipe Volume (m³) = 382.648


Network Design Table for Surface Network 3

« - Indicates pipe capacity < flow
















| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Section | Type | Auto Design |
|-------|------------|----------|-------------|-------------|-------------|-----------------|--------|----------|----------|--------------|------|---|
| 1.000 | 58.466 | 0.130 | 450.0 | 0.529 | 5.00 | 0.0 | 0.600 | o | 600 | Pipe/Conduit | |  |
| 1.001 | 72.952 | 0.162 | 450.0 | 0.277 | 0.00 | 0.0 | 0.600 | o | 600 | Pipe/Conduit | |  |
| 1.002 | 80.000 | 0.178 | 450.0 | 0.261 | 0.00 | 0.0 | 0.600 | o | 600 | Pipe/Conduit | |  |
| 1.003 | 81.398 | 0.181 | 450.0 | 0.300 | 0.00 | 0.0 | 0.600 | o | 600 | Pipe/Conduit | |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|--------------|-------------|-----------|---------------|-------------------|------------|----------------|-----------|-----------|------------|
| 1.000 | 50.00 | 5.85 | 6.923 | 0.529 | 0.0 | 0.0 | 0.0 | 1.14 | 322.7 | 71.6 |
| 1.001 | 50.00 | 6.92 | 6.793 | 0.805 | 0.0 | 0.0 | 0.0 | 1.14 | 322.7 | 109.0 |
| 1.002 | 50.00 | 8.09 | 6.631 | 1.066 | 0.0 | 0.0 | 0.0 | 1.14 | 322.7 | 144.3 |
| 1.003 | 50.00 | 9.28 | 6.453 | 1.366 | 0.0 | 0.0 | 0.0 | 1.14 | 322.7 | 184.9 |


| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 1 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0003 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

Network Design Table for Surface Network 3

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Section Type | Auto Design |
|-------|------------|----------|-------------|-------------|-------------|-----------------|--------|----------|----------|--------------|---|
| 2.000 | 90.000 | 0.400 | 225.0 | 0.484 | 5.00 | 0.0 | 0.600 | o | 450 | Pipe/Conduit |  |
| 2.001 | 80.000 | 0.356 | 225.0 | 0.266 | 0.00 | 0.0 | 0.600 | o | 450 | Pipe/Conduit |  |
| 2.002 | 15.767 | 0.212 | 74.3 | 0.000 | 0.00 | 0.0 | 0.600 | o | 450 | Pipe/Conduit |  |
| 1.004 | 4.500 | 0.010 | 450.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 1.005 | 4.500 | 0.010 | 450.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 3.000 | 30.000 | 0.067 | 450.0 | 1.428 | 5.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 3.001 | 80.000 | 0.178 | 450.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 4.000 | 23.000 | 1.317 | 17.5 | 1.370 | 5.00 | 0.0 | 0.600 | o | 600 | Pipe/Conduit |  |
| 3.002 | 64.734 | 0.144 | 450.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 3.003 | 60.000 | 0.133 | 450.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 3.004 | 65.266 | 0.145 | 450.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 750 | Pipe/Conduit |  |
| 5.000 | 103.300 | 0.459 | 225.0 | 2.766 | 5.00 | 0.0 | 0.600 | o | 900 | Pipe/Conduit |  |
| 5.001 | 10.651 | 0.047 | 225.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 900 | Pipe/Conduit |  |
| 5.002 | 73.947 | 0.594 | 124.6 | 0.000 | 0.00 | 0.0 | 0.600 | o | 900 | Pipe/Conduit |  |
| 1.006 | 12.199 | 0.027 | 450.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 900 | Pipe/Conduit |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL E (m) | I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|--------------|-------------|-------------|-------------|-------------------|------------|----------------|-----------|-----------|------------|
| 2.000 | 50.00 | 6.11 | 7.818 | 0.484 | 0.0 | 0.0 | 0.0 | 1.35 | 214.9 | 65.6 |
| 2.001 | 50.00 | 7.10 | 7.418 | 0.751 | 0.0 | 0.0 | 0.0 | 1.35 | 214.9 | 101.7 |
| 2.002 | 50.00 | 7.21 | 7.062 | 0.751 | 0.0 | 0.0 | 0.0 | 2.36 | 375.5 | 101.7 |
| 1.004 | 50.00 | 9.33 | 6.122 | 2.117 | 0.0 | 0.0 | 0.0 | 1.31 | 579.9 | 286.6 |
| 1.005 | 50.00 | 9.39 | 6.112 | 2.117 | 0.0 | 0.0 | 0.0 | 1.31 | 579.9 | 286.6 |
| 3.000 | 50.00 | 5.38 | 6.769 | 1.428 | 0.0 | 0.0 | 0.0 | 1.31 | 579.9 | 193.4 |
| 3.001 | 50.00 | 6.40 | 6.702 | 1.428 | 0.0 | 0.0 | 0.0 | 1.31 | 579.9 | 193.4 |
| 4.000 | 50.00 | 5.07 | 7.991 | 1.370 | 0.0 | 0.0 | 0.0 | 5.85 | 1652.9 | 185.5 |
| 3.002 | 50.00 | 7.22 | 6.524 | 2.798 | 0.0 | 0.0 | 0.0 | 1.31 | 579.9 | 378.9 |
| 3.003 | 50.00 | 7.98 | 6.380 | 2.798 | 0.0 | 0.0 | 0.0 | 1.31 | 579.9 | 378.9 |
| 3.004 | 50.00 | 8.81 | 6.247 | 2.798 | 0.0 | 0.0 | 0.0 | 1.31 | 579.9 | 378.9 |
| 5.000 | 50.00 | 5.83 | 7.900 | 2.766 | 0.0 | 0.0 | 0.0 | 2.08 | 1326.3 | 374.6 |
| 5.001 | 50.00 | 5.91 | 7.441 | 2.766 | 0.0 | 0.0 | 0.0 | 2.08 | 1326.3 | 374.6 |
| 5.002 | 50.00 | 6.35 | 7.394 | 2.766 | 0.0 | 0.0 | 0.0 | 2.81 | 1785.2 | 374.6 |
| 1.006 | 50.00 | 9.53 | 5.952 | 7.681 | 0.0 | 0.0 | 0.0 | 1.47 | 935.5 | 1040.1 |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 2 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0003 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

Area Summary for Surface Network 3

| Pipe Number | PIMP Type | PIMP Name | PIMP (%) | Gross Area (ha) | Imp. Area (ha) | Pipe Total (ha) |
|-------------|-----------|-----------|----------|-----------------|----------------|-----------------|
| 1.000 | User | - | 100 | 0.529 | 0.529 | 0.529 |
| 1.001 | User | - | 100 | 0.277 | 0.277 | 0.277 |
| 1.002 | User | - | 100 | 0.261 | 0.261 | 0.261 |
| 1.003 | User | - | 100 | 0.300 | 0.300 | 0.300 |
| 2.000 | User | - | 100 | 0.484 | 0.484 | 0.484 |
| 2.001 | User | - | 100 | 0.266 | 0.266 | 0.266 |
| 2.002 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 1.004 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 1.005 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 3.000 | User | - | 100 | 1.428 | 1.428 | 1.428 |
| 3.001 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 4.000 | User | - | 100 | 1.370 | 1.370 | 1.370 |
| 3.002 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 3.003 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 3.004 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 5.000 | User | - | 100 | 2.766 | 2.766 | 2.766 |
| 5.001 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 5.002 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 1.006 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| | | | | Total | Total | Total |
| | | | | 7.681 | 7.681 | 7.681 |

Free Flowing Outfall Details for Surface Network 3

| Outfall Pipe Number | Outfall Name | C. Level (m) | I. Level (m) | Min I. Level (m) | D,L (mm) | W (mm) |
|---------------------|--------------|--------------|--------------|------------------|----------|--------|
| 1.006 | S32 | 9.740 | 5.925 | 0.000 | 1800 | 0 |


Simulation Criteria for Surface Network 3

| | | | |
|---------------------------------|-------|-------------------------------------|-------|
| Volumetric Runoff Coeff | 0.750 | Additional Flow - % of Total Flow | 0.000 |
| Areal Reduction Factor | 1.000 | MADD Factor * 10m³/ha Storage | 2.000 |
| Hot Start (mins) | 0 | Inlet Coefficient | 0.800 |
| Hot Start Level (mm) | 0 | Flow per Person per Day (l/per/day) | 0.000 |
| Manhole Headloss Coeff (Global) | 0.500 | Run Time (mins) | 60 |
| Foul Sewage per hectare (l/s) | 0.000 | Output Interval (mins) | 1 |

Number of Input Hydrographs 0 Number of Storage Structures 0
Number of Online Controls 0 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0


Synthetic Rainfall Details

| | | | |
|--|-----|------------|--------|
| Rainfall Model | FSR | M5-60 (mm) | 17.900 |
| Return Period (years) | 100 | Ratio R | 0.350 |
| Region England and Wales Profile Type Summer | | | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 3 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0003 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

Synthetic Rainfall Details

Cv (Summer) 0.750 Storm Duration (mins) 30
Cv (Winter) 0.840

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 4 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0003 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 3

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 0
Number of Online Controls 0 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0


Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 17.900 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON


Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 30

| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surcharge | First (Y) Flood | First (Z) Overflow | Overflow Act. | Water Level (m) |
|-------|------------|--------|---------------|----------------|---------------------|-----------------|--------------------|---------------|-----------------|
| 1.000 | S39 15 | Winter | 1 | +0% | 30/15 | Winter | | | 7.121 |
| 1.001 | S40 15 | Winter | 1 | +0% | 30/15 | Summer | | | 7.013 |
| 1.002 | S41 15 | Winter | 1 | +0% | 30/15 | Summer | | | 6.891 |
| 1.003 | S42 15 | Winter | 1 | +0% | 30/15 | Summer | | | 6.838 |
| 2.000 | S33 15 | Winter | 1 | +0% | 100/15 | Summer | | | 7.981 |
| 2.001 | S34 15 | Winter | 1 | +0% | 100/15 | Summer | | | 7.614 |
| 2.002 | S35 15 | Winter | 1 | +0% | 100/15 | Summer | | | 7.229 |
| 1.004 | S36 15 | Winter | 1 | +0% | 30/15 | Summer | | | 6.788 |
| 1.005 | S37 15 | Winter | 1 | +0% | 30/15 | Summer | | | 6.774 |
| 3.000 | S26 15 | Winter | 1 | +0% | 30/15 | Summer | | | 7.107 |
| 3.001 | S27 15 | Winter | 1 | +0% | 30/15 | Summer | | | 7.034 |
| 4.000 | S38 15 | Winter | 1 | +0% | 100/15 | Summer | | | 8.142 |
| 3.002 | S28 15 | Winter | 1 | +0% | 30/15 | Summer | | | 6.945 |
| 3.003 | S29 15 | Winter | 1 | +0% | 30/15 | Summer | | | 6.898 |
| 3.004 | S30 15 | Winter | 1 | +0% | 30/15 | Summer | | | 6.841 |
| 5.000 | S43 15 | Winter | 1 | +0% | 100/15 | Summer | | | 8.222 |
| 5.001 | S44 15 | Winter | 1 | +0% | 100/15 | Summer | | | 7.851 |
| 5.002 | S45 15 | Winter | 1 | +0% | 100/15 | Winter | | | 7.665 |
| 1.006 | S31 15 | Winter | 1 | +0% | 30/15 | Summer | | | 6.762 |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 5 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0003 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 3

| PN | US/MH Name | Surcharged Flooded | | Flow / Overflow Cap. (l/s) | Half Drain Time (mins) | Pipe Flow (l/s) | Status | Level Exceeded |
|-------|---------------|--------------------|----------------|----------------------------------|------------------------------|-----------------------|--------|-------------------|
| | | Depth (m) | Volume (m³) | | | | | |
| 1.000 | S39 | -0.402 | 0.000 | 0.21 | | 59.8 | OK | |
| 1.001 | S40 | -0.380 | 0.000 | 0.27 | | 79.6 | OK | |
| 1.002 | S41 | -0.340 | 0.000 | 0.30 | | 89.7 | OK | |
| 1.003 | S42 | -0.215 | 0.000 | 0.35 | | 103.0 | OK | |
| 2.000 | S33 | -0.286 | 0.000 | 0.27 | | 54.0 | OK | |
| 2.001 | S34 | -0.254 | 0.000 | 0.38 | | 76.2 | OK | |
| 2.002 | S35 | -0.283 | 0.000 | 0.29 | | 76.3 | OK | |
| 1.004 | S36 | -0.085 | 0.000 | 0.50 | | 175.8 | OK | |
| 1.005 | S37 | -0.088 | 0.000 | 0.52 | | 180.6 | OK | |
| 3.000 | S26 | -0.412 | 0.000 | 0.36 | | 163.6 | OK | |
| 3.001 | S27 | -0.418 | 0.000 | 0.29 | | 151.8 | OK | |
| 4.000 | S38 | -0.450 | 0.000 | 0.14 | | 161.9 | OK | |
| 3.002 | S28 | -0.329 | 0.000 | 0.53 | | 271.0 | OK | |
| 3.003 | S29 | -0.233 | 0.000 | 0.45 | | 227.5 | OK | |
| 3.004 | S30 | -0.156 | 0.000 | 0.36 | | 184.2 | OK | |
| 5.000 | S43 | -0.578 | 0.000 | 0.26 | | 314.6 | OK | |
| 5.001 | S44 | -0.490 | 0.000 | 0.43 | | 308.8 | OK | |
| 5.002 | S45 | -0.628 | 0.000 | 0.20 | | 306.0 | OK | |
| 1.006 | S31 | -0.090 | 0.000 | 1.22 | | 531.8 | OK | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 6 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0003 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 3

Simulation Criteria


| | | | |
|---------------------------------|-------|--|-------|
| Areal Reduction Factor | 1.000 | Additional Flow - % of Total Flow | 0.000 |
| Hot Start (mins) | 0 | MADD Factor * 10m ³ /ha Storage | 2.000 |
| Hot Start Level (mm) | 0 | Inlet Coefficient | 0.800 |
| Manhole Headloss Coeff (Global) | 0.500 | Flow per Person per Day (l/per/day) | 0.000 |
| Foul Sewage per hectare (l/s) | 0.000 | | |

| | | | |
|-----------------------------|---|------------------------------|---|
| Number of Input Hydrographs | 0 | Number of Storage Structures | 0 |
| Number of Online Controls | 0 | Number of Time/Area Diagrams | 0 |
| Number of Offline Controls | 0 | Number of Real Time Controls | 0 |

Synthetic Rainfall Details


| | | | |
|------------------------------------|----------------------|----------------------|-------|
| Rainfall Model | FSR | Ratio R | 0.350 |
| Region | England and Wales | Cv (Summer) | 0.750 |
| M5-60 (mm) | | 17.900 Cv (Winter) | 0.840 |
| Margin for Flood Risk Warning (mm) | | | 300.0 |
| Analysis Timestep | 2.5 Second | Increment (Extended) | |
| DTS Status | | | OFF |
| DVD Status | | | ON |
| Inertia Status | | | ON |
| Profile(s) | Summer and Winter | | |
| Duration(s) (mins) | 15, 30, 60, 120, 180 | | |
| Return Period(s) (years) | 1, 30, 100 | | |
| Climate Change (%) | 0, 0, 30 | | |

| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surcharge | First (Y) Flood | First (Z) Overflow | Overflow Act. | Water Level (m) |
|-------|------------|-----------|---------------|----------------|---------------------|-----------------|--------------------|---------------|-----------------|
| 1.000 | S39 | 15 Winter | 30 | +0% | 30/15 Winter | | | | 7.525 |
| 1.001 | S40 | 15 Winter | 30 | +0% | 30/15 Summer | | | | 7.467 |
| 1.002 | S41 | 15 Winter | 30 | +0% | 30/15 Summer | | | | 7.431 |
| 1.003 | S42 | 15 Winter | 30 | +0% | 30/15 Summer | | | | 7.381 |
| 2.000 | S33 | 15 Winter | 30 | +0% | 100/15 Summer | | | | 8.096 |
| 2.001 | S34 | 15 Winter | 30 | +0% | 100/15 Summer | | | | 7.778 |
| 2.002 | S35 | 15 Winter | 30 | +0% | 100/15 Summer | | | | 7.372 |
| 1.004 | S36 | 15 Winter | 30 | +0% | 30/15 Summer | | | | 7.305 |
| 1.005 | S37 | 15 Winter | 30 | +0% | 30/15 Summer | | | | 7.286 |
| 3.000 | S26 | 15 Winter | 30 | +0% | 30/15 Summer | | | | 7.863 |
| 3.001 | S27 | 15 Winter | 30 | +0% | 30/15 Summer | | | | 7.823 |
| 4.000 | S38 | 15 Winter | 30 | +0% | 100/15 Summer | | | | 8.236 |
| 3.002 | S28 | 15 Winter | 30 | +0% | 30/15 Summer | | | | 7.771 |
| 3.003 | S29 | 15 Winter | 30 | +0% | 30/15 Summer | | | | 7.624 |
| 3.004 | S30 | 15 Winter | 30 | +0% | 30/15 Summer | | | | 7.457 |
| 5.000 | S43 | 15 Winter | 30 | +0% | 100/15 Summer | | | | 8.447 |
| 5.001 | S44 | 15 Winter | 30 | +0% | 100/15 Summer | | | | 8.182 |
| 5.002 | S45 | 15 Winter | 30 | +0% | 100/15 Winter | | | | 7.826 |
| 1.006 | S31 | 15 Winter | 30 | +0% | 30/15 Summer | | | | 7.267 |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 7 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0003 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 3

| PN | US/MH Name | Surcharged Flooded | | Flow / Cap. | Overflow (l/s) | Half Drain Time (mins) | Pipe Flow (l/s) | Status | Level Exceeded |
|-------|---------------|--------------------|-----------------------------|----------------|-------------------|------------------------------|-----------------------|------------|-------------------|
| | | Depth (m) | Volume (m ³) | | | | | | |
| 1.000 | S39 | 0.003 | 0.000 | 0.50 | | | 144.9 | SURCHARGED | |
| 1.001 | S40 | 0.074 | 0.000 | 0.62 | | | 181.9 | SURCHARGED | |
| 1.002 | S41 | 0.200 | 0.000 | 0.53 | | | 157.1 | SURCHARGED | |
| 1.003 | S42 | 0.328 | 0.000 | 0.60 | | | 178.8 | SURCHARGED | |
| 2.000 | S33 | -0.172 | 0.000 | 0.65 | | | 132.3 | OK | |
| 2.001 | S34 | -0.089 | 0.000 | 0.96 | | | 193.0 | OK | |
| 2.002 | S35 | -0.140 | 0.000 | 0.73 | | | 189.4 | OK | |
| 1.004 | S36 | 0.433 | 0.000 | 1.00 | | | 349.2 | SURCHARGED | |
| 1.005 | S37 | 0.424 | 0.000 | 1.00 | | | 350.6 | SURCHARGED | |
| 3.000 | S26 | 0.345 | 0.000 | 0.84 | | | 377.5 | SURCHARGED | |
| 3.001 | S27 | 0.371 | 0.000 | 0.61 | | | 314.2 | SURCHARGED | |
| 4.000 | S38 | -0.356 | 0.000 | 0.35 | | | 396.9 | OK | |
| 3.002 | S28 | 0.497 | 0.000 | 1.21 | | | 615.2 | SURCHARGED | |
| 3.003 | S29 | 0.494 | 0.000 | 1.15 | | | 575.9 | SURCHARGED | |
| 3.004 | S30 | 0.460 | 0.000 | 1.08 | | | 545.8 | SURCHARGED | |
| 5.000 | S43 | -0.353 | 0.000 | 0.65 | | | 771.8 | OK | |
| 5.001 | S44 | -0.159 | 0.000 | 1.00 | | | 720.8 | OK | |
| 5.002 | S45 | -0.468 | 0.000 | 0.47 | | | 719.6 | OK | |
| 1.006 | S31 | 0.415 | 0.000 | 3.60 | | | 1570.7 | SURCHARGED | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 8 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0003 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 3

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 0
Number of Online Controls 0 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0


Synthetic Rainfall Details

Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 17.900 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON


Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 30

| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surcharge | First (Y) Flood | First (Z) Overflow | Overflow Act. | Water Level (m) |
|-------|------------|--------|---------------|----------------|---------------------|-----------------|--------------------|---------------|-----------------|
| 1.000 | S39 15 | Winter | 100 | +30% | 30/15 | Winter | | | 8.869 |
| 1.001 | S40 15 | Winter | 100 | +30% | 30/15 | Summer | | | 8.824 |
| 1.002 | S41 15 | Winter | 100 | +30% | 30/15 | Summer | | | 8.736 |
| 1.003 | S42 15 | Winter | 100 | +30% | 30/15 | Summer | | | 8.557 |
| 2.000 | S33 15 | Winter | 100 | +30% | 100/15 | Summer | | | 9.027 |
| 2.001 | S34 15 | Winter | 100 | +30% | 100/15 | Summer | | | 8.817 |
| 2.002 | S35 15 | Winter | 100 | +30% | 100/15 | Summer | | | 8.424 |
| 1.004 | S36 15 | Winter | 100 | +30% | 30/15 | Summer | | | 8.263 |
| 1.005 | S37 15 | Winter | 100 | +30% | 30/15 | Summer | | | 8.204 |
| 3.000 | S26 15 | Winter | 100 | +30% | 30/15 | Summer | | | 9.496 |
| 3.001 | S27 15 | Winter | 100 | +30% | 30/15 | Summer | | | 9.436 |
| 4.000 | S38 15 | Winter | 100 | +30% | 100/15 | Summer | | | 9.686 |
| 3.002 | S28 15 | Winter | 100 | +30% | 30/15 | Summer | | | 9.316 |
| 3.003 | S29 15 | Winter | 100 | +30% | 30/15 | Summer | | | 8.958 |
| 3.004 | S30 15 | Winter | 100 | +30% | 30/15 | Summer | | | 8.557 |
| 5.000 | S43 15 | Winter | 100 | +30% | 100/15 | Summer | | | 9.076 |
| 5.001 | S44 15 | Winter | 100 | +30% | 100/15 | Summer | | | 8.550 |
| 5.002 | S45 15 | Winter | 100 | +30% | 100/15 | Winter | | | 8.355 |
| 1.006 | S31 15 | Winter | 100 | +30% | 30/15 | Summer | | | 8.095 |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 9 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0003 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 3

| PN | US/MH Name | Surcharged Flooded | | Flow / Overflow Cap. | Half Drain Time (mins) | Pipe Flow (l/s) | Status | Level Exceeded |
|-------|---------------|--------------------|-----------------------------|----------------------------|------------------------------|-----------------------|------------|-------------------|
| | | Depth (m) | Volume (m ³) | | | | | |
| 1.000 | S39 | 1.346 | 0.000 | 0.72 | | 206.6 | SURCHARGED | |
| 1.001 | S40 | 1.431 | 0.000 | 0.95 | | 278.2 | SURCHARGED | |
| 1.002 | S41 | 1.506 | 0.000 | 1.08 | | 319.8 | SURCHARGED | |
| 1.003 | S42 | 1.504 | 0.000 | 1.24 | | 367.8 | SURCHARGED | |
| 2.000 | S33 | 0.759 | 0.000 | 0.96 | | 195.3 | SURCHARGED | |
| 2.001 | S34 | 0.949 | 0.000 | 1.31 | | 265.4 | SURCHARGED | |
| 2.002 | S35 | 0.912 | 0.000 | 0.94 | | 243.6 | SURCHARGED | |
| 1.004 | S36 | 1.391 | 0.000 | 1.72 | | 603.7 | SURCHARGED | |
| 1.005 | S37 | 1.342 | 0.000 | 1.73 | | 605.1 | SURCHARGED | |
| 3.000 | S26 | 1.978 | 0.000 | 1.26 | | 565.1 | SURCHARGED | |
| 3.001 | S27 | 1.984 | 0.000 | 1.00 | | 521.2 | FLOOD RISK | |
| 4.000 | S38 | 1.095 | 0.000 | 0.53 | | 609.4 | FLOOD RISK | |
| 3.002 | S28 | 2.042 | 0.000 | 1.86 | | 945.1 | SURCHARGED | |
| 3.003 | S29 | 1.827 | 0.000 | 1.81 | | 907.2 | SURCHARGED | |
| 3.004 | S30 | 1.560 | 0.000 | 1.73 | | 880.3 | SURCHARGED | |
| 5.000 | S43 | 0.276 | 0.000 | 1.02 | | 1217.9 | SURCHARGED | |
| 5.001 | S44 | 0.210 | 0.000 | 1.70 | | 1230.5 | SURCHARGED | |
| 5.002 | S45 | 0.061 | 0.000 | 0.77 | | 1183.3 | SURCHARGED | |
| 1.006 | S31 | 1.243 | 0.000 | 5.86 | | 2554.8 | SURCHARGED | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 0 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0004 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Surface Network 4

Pipe Sizes STANDARD Manhole Sizes STANDARD

| | | | |
|--|--------|---------------------------------------|-------|
| FSR Rainfall Model - England and Wales | | | |
| Return Period (years) | 100 | PIMP (%) | 100 |
| M5-60 (mm) | 17.900 | Add Flow / Climate Change (%) | 0 |
| Ratio R | 0.350 | Minimum Backdrop Height (m) | 0.200 |
| Maximum Rainfall (mm/hr) | 50 | Maximum Backdrop Height (m) | 1.500 |
| Maximum Time of Concentration (mins) | 30 | Min Design Depth for Optimisation (m) | 1.200 |
| Foul Sewage (l/s/ha) | 0.000 | Min Vel for Auto Design only (m/s) | 1.00 |
| Volumetric Runoff Coeff. | 0.750 | Min Slope for Optimisation (1:X) | 500 |

Designed with Level Soffits






Time Area Diagram for Surface Network 4

| Time (mins) | Area (ha) | Time (mins) | Area (ha) |
|-------------|-----------|-------------|-----------|
| 0-4 | 1.382 | 4-8 | 1.111 |

Total Area Contributing (ha) = 2.493


Total Pipe Volume (m³) = 48.495

Network Design Table for Surface Network 4



| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Section | Type | Auto Design |
|-------|------------|----------|-------------|-------------|-------------|-----------------|--------|----------|----------|--------------|------|---|
| 1.000 | 90.000 | 0.300 | 300.0 | 1.173 | 5.00 | 0.0 | 0.600 | o | 525 | Pipe/Conduit | |  |
| 1.001 | 39.494 | 0.132 | 300.0 | 0.409 | 0.00 | 0.0 | 0.600 | o | 525 | Pipe/Conduit | |  |
| 2.000 | 90.000 | 0.400 | 225.0 | 0.578 | 5.00 | 0.0 | 0.600 | o | 375 | Pipe/Conduit | |  |
| 2.001 | 10.606 | 0.047 | 225.2 | 0.121 | 0.00 | 0.0 | 0.600 | o | 450 | Pipe/Conduit | |  |
| 2.002 | 16.000 | 0.515 | 31.1 | 0.000 | 0.00 | 0.0 | 0.600 | o | 450 | Pipe/Conduit | |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|--------------|-------------|-----------|---------------|-------------------|------------|----------------|-----------|-----------|------------|
| 1.000 | 50.00 | 6.16 | 5.761 | 1.173 | 0.0 | 0.0 | 0.0 | 1.29 | 278.8 | 158.9 |
| 1.001 | 50.00 | 6.68 | 5.461 | 1.582 | 0.0 | 0.0 | 0.0 | 1.29 | 278.8 | 214.3 |
| 2.000 | 50.00 | 6.25 | 7.712 | 0.578 | 0.0 | 0.0 | 0.0 | 1.20 | 133.0 | 78.3 |
| 2.001 | 50.00 | 6.38 | 7.312 | 0.699 | 0.0 | 0.0 | 0.0 | 1.35 | 214.8 | 94.7 |
| 2.002 | 50.00 | 6.45 | 7.265 | 0.699 | 0.0 | 0.0 | 0.0 | 3.66 | 581.8 | 94.7 |


| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 1 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0004 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

Network Design Table for Surface Network 4

| PN | Length (m) | Fall (m) | Slope (1:X) | I.Area (ha) | T.E. (mins) | Base Flow (l/s) | k (mm) | HYD SECT | DIA (mm) | Section | Type | Auto Design |
|-------|---------------|-------------|----------------|----------------|----------------|--------------------|-----------|-------------|-------------|--------------|------|---|
| 1.002 | 5.000 | 0.017 | 300.0 | 0.212 | 0.00 | 0.0 | 0.600 | o | 600 | Pipe/Conduit | |  |
| 1.003 | 17.250 | 0.058 | 300.0 | 0.000 | 0.00 | 0.0 | 0.600 | o | 600 | Pipe/Conduit | |  |

Network Results Table

| PN | Rain (mm/hr) | T.C. (mins) | US/IL (m) | Σ I.Area (ha) | Σ Base Flow (l/s) | Foul (l/s) | Add Flow (l/s) | Vel (m/s) | Cap (l/s) | Flow (l/s) |
|-------|-----------------|----------------|--------------|------------------|----------------------|---------------|-------------------|--------------|--------------|---------------|
| 1.002 | 50.00 | 6.74 | 5.254 | 2.493 | 0.0 | 0.0 | 0.0 | 1.40 | 396.0 | 337.6 |
| 1.003 | 50.00 | 6.94 | 5.238 | 2.493 | 0.0 | 0.0 | 0.0 | 1.40 | 396.0 | 337.6 |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 2 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0004 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

Area Summary for Surface Network 4


| Pipe Number | PIMP Type | PIMP Name | PIMP (%) | Gross Area (ha) | Imp. Area (ha) | Pipe Total (ha) |
|-------------|-----------|-----------|----------|-----------------|----------------|-----------------|
| 1.000 | User | - | 100 | 0.423 | 0.423 | 0.423 |
| | User | - | 100 | 0.751 | 0.751 | 1.173 |
| 1.001 | User | - | 100 | 0.409 | 0.409 | 0.409 |
| 2.000 | User | - | 100 | 0.333 | 0.333 | 0.333 |
| | User | - | 100 | 0.245 | 0.245 | 0.578 |
| 2.001 | User | - | 100 | 0.121 | 0.121 | 0.121 |
| 2.002 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| 1.002 | User | - | 100 | 0.212 | 0.212 | 0.212 |
| 1.003 | - | - | 100 | 0.000 | 0.000 | 0.000 |
| | | | | Total | Total | Total |
| | | | | 2.493 | 2.493 | 2.493 |

Simulation Criteria for Surface Network 4

| | | | |
|---------------------------------|-------|--|-------|
| Volumetric Runoff Coeff | 0.750 | Additional Flow - % of Total Flow | 0.000 |
| Areal Reduction Factor | 1.000 | MADD Factor * 10m ³ /ha Storage | 2.000 |
| Hot Start (mins) | 0 | Inlet Coefficient | 0.800 |
| Hot Start Level (mm) | 0 | Flow per Person per Day (l/per/day) | 0.000 |
| Manhole Headloss Coeff (Global) | 0.500 | Run Time (mins) | 60 |
| Foul Sewage per hectare (l/s) | 0.000 | Output Interval (mins) | 1 |
| Number of Input Hydrographs | 0 | Number of Storage Structures | 0 |
| Number of Online Controls | 0 | Number of Time/Area Diagrams | 0 |
| Number of Offline Controls | 0 | Number of Real Time Controls | 0 |

Synthetic Rainfall Details

| | | | |
|-----------------------|-------------------|-----------------------|--------|
| Rainfall Model | FSR | Profile Type | Summer |
| Return Period (years) | 100 | Cv (Summer) | 0.750 |
| Region | England and Wales | Cv (Winter) | 0.840 |
| M5-60 (mm) | 17.900 | Storm Duration (mins) | 30 |
| Ratio R | 0.350 | | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 3 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0004 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 4

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 0
Number of Online Controls 0 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 17.900 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 30


| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surcharge | First (Y) Flood | First (Z) Overflow | Water Level (m) |
|-------|------------|--------|---------------|----------------|---------------------|-----------------|--------------------|-----------------|
| 1.000 | S46 15 | Winter | 1 | +0% | 30/15 Summer | 100/15 Winter | | 6.036 |
| 1.001 | S47 15 | Winter | 1 | +0% | 30/15 Summer | | | 5.883 |
| 2.000 | S52 15 | Winter | 1 | +0% | 30/15 Summer | 100/15 Winter | | 7.910 |
| 2.001 | S53 15 | Winter | 1 | +0% | 30/15 Winter | | | 7.535 |
| 2.002 | S54 15 | Winter | 1 | +0% | | | | 7.394 |
| 1.002 | S48 15 | Winter | 1 | +0% | 30/15 Summer | | | 5.815 |
| 1.003 | S49 15 | Winter | 1 | +0% | 30/15 Summer | | | 5.625 |

| PN | US/MH Name | Surcharged Flooded | | | Half Drain Pipe | | Level Exceeded |
|-------|------------|--------------------|--------------------------|----------------------------|-----------------|------------------------|----------------|
| | | Depth (m) | Volume (m ³) | Flow / Overflow Cap. (l/s) | Time (mins) | Pipe Flow (l/s) Status | |
| 1.000 | S46 | -0.250 | 0.000 | 0.50 | | 129.7 | OK 1 |
| 1.001 | S47 | -0.102 | 0.000 | 0.58 | | 139.5 | OK |
| 2.000 | S52 | -0.177 | 0.000 | 0.50 | | 63.1 | OK 1 |
| 2.001 | S53 | -0.227 | 0.000 | 0.49 | | 74.5 | OK |
| 2.002 | S54 | -0.321 | 0.000 | 0.18 | | 74.3 | OK |
| 1.002 | S48 | -0.039 | 0.000 | 1.00 | | 215.2 | OK |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 4 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0004 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 4

| PN | US/MH Name | Surcharged Flooded | | Half Drain Pipe | | | Level Exceeded |
|-------|---------------|--------------------|-----------------------------|-------------------------------|----------------|---------------|-------------------|
| | | Depth (m) | Volume (m ³) | Flow / Overflow Cap. (l/s) | Time (mins) | Flow (l/s) | |
| 1.003 | S49 | -0.212 | 0.000 | 0.75 | | 215.2 | OK |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 5 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0004 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 4

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 0
Number of Online Controls 0 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 17.900 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 30


| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surge | First (Y) Flood | First (Z) Overflow | Water Level (m) |
|-------|------------|-----------|---------------|----------------|-----------------|-----------------|--------------------|-----------------|
| 1.000 | S46 | 15 Winter | 30 | +0% | 30/15 Summer | 100/15 Winter | | 7.171 |
| 1.001 | S47 | 15 Winter | 30 | +0% | 30/15 Summer | | | 6.753 |
| 2.000 | S52 | 15 Winter | 30 | +0% | 30/15 Summer | 100/15 Winter | | 8.322 |
| 2.001 | S53 | 15 Winter | 30 | +0% | 30/15 Winter | | | 7.777 |
| 2.002 | S54 | 15 Winter | 30 | +0% | | | | 7.463 |
| 1.002 | S48 | 15 Winter | 30 | +0% | 30/15 Summer | | | 6.416 |
| 1.003 | S49 | 15 Winter | 30 | +0% | 30/15 Summer | | | 6.082 |

| PN | US/MH Name | Surcharged Depth (m) | Flooded Volume (m ³) | Flow / Overflow Cap. (l/s) | Half Drain Time (mins) | Pipe Flow (l/s) | Status | Level Exceeded |
|-------|------------|----------------------|----------------------------------|----------------------------|------------------------|-----------------|------------|----------------|
| 1.000 | S46 | 0.885 | 0.000 | 1.11 | | 289.9 | SURCHARGED | 1 |
| 1.001 | S47 | 0.767 | 0.000 | 1.54 | | 373.4 | SURCHARGED | |
| 2.000 | S52 | 0.235 | 0.000 | 1.15 | | 146.6 | SURCHARGED | 1 |
| 2.001 | S53 | 0.015 | 0.000 | 1.05 | | 158.8 | SURCHARGED | |
| 2.002 | S54 | -0.252 | 0.000 | 0.39 | | 159.7 | OK | |
| 1.002 | S48 | 0.562 | 0.000 | 2.65 | | 569.4 | SURCHARGED | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 6 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0004 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Surface Network 4

| PN | US/MH Name | Surcharged Depth (m) | Flooded Volume (m ³) | Flow / Overflow Cap. (l/s) | Half Drain Time (mins) | Pipe Flow (l/s) | Status | Level Exceeded |
|-------|------------|----------------------|----------------------------------|----------------------------|------------------------|-----------------|------------|----------------|
| 1.003 | S49 | 0.244 | 0.000 | 1.97 | | 569.6 | SURCHARGED | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 7 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0004 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 4

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0 Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 0
Number of Online Controls 0 Number of Time/Area Diagrams 0
Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model FSR Ratio R 0.350
Region England and Wales Cv (Summer) 0.750
M5-60 (mm) 17.900 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180
Return Period(s) (years) 1, 30, 100
Climate Change (%) 0, 0, 30

| PN | US/MH Name | Storm | Return Period | Climate Change | First (X) Surge | First (Y) Flood | First (Z) Overflow | Water Level (m) |
|-------|------------|-----------|---------------|----------------|-----------------|-----------------|--------------------|-----------------|
| 1.000 | S46 | 15 Winter | 100 | +30% | 30/15 Summer | 100/15 Winter | | 9.196 |
| 1.001 | S47 | 15 Winter | 100 | +30% | 30/15 Summer | | | 8.269 |
| 2.000 | S52 | 15 Winter | 100 | +30% | 30/15 Summer | 100/15 Winter | | 9.289 |
| 2.001 | S53 | 15 Winter | 100 | +30% | 30/15 Winter | | | 7.923 |
| 2.002 | S54 | 15 Winter | 100 | +30% | | | | 7.665 |
| 1.002 | S48 | 15 Winter | 100 | +30% | 30/15 Summer | | | 7.446 |
| 1.003 | S49 | 15 Winter | 100 | +30% | 30/15 Summer | | | 6.598 |


| PN | US/MH Name | Surcharged Depth (m) | Flooded Volume (m ³) | Flow / Cap. (l/s) | Half Drain Time (mins) | Pipe Flow (l/s) | Status | Level Exceeded |
|-------|------------|----------------------|----------------------------------|-------------------|------------------------|-----------------|------------|----------------|
| 1.000 | S46 | 2.910 | 1.651 | 1.75 | | 457.0 | FLOOD | 1 |
| 1.001 | S47 | 2.283 | 0.000 | 2.44 | | 591.1 | SURCHARGED | |
| 2.000 | S52 | 1.202 | 1.835 | 1.81 | | 229.7 | FLOOD | 1 |
| 2.001 | S53 | 0.161 | 0.000 | 1.75 | | 266.3 | SURCHARGED | |
| 2.002 | S54 | -0.050 | 0.000 | 0.67 | | 270.4 | OK | |
| 1.002 | S48 | 1.591 | 0.000 | 4.25 | | 914.9 | SURCHARGED | |

| | | |
|--|--|---|
| Clarkebond (UK) Limited | | Page 8 |
| 129 Cumberland Road Bristol BS1 6UY | SEAH-CLK-ZZ-EX.ZZ-CA-C-0004 |  |
| Date 11/04/2022 File SEAH-CLK-ZZ-EX.ZZ-CA-C-... | Designed by Justin Horsley Checked by Samuel Ihle | |
| XP Solutions | Network 2020.1 | |

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Network 4

| PN | US/MH Name | Surcharged Flooded | | Half Drain | | Pipe | Status | Level Exceeded |
|-------|---------------|--------------------|-----------------------------|-------------------------------------|----------------|---------------|------------|-------------------|
| | | Depth (m) | Volume (m ³) | Flow / Overflow Cap. (l/s) | Time (mins) | Flow (l/s) | | |
| 1.003 | S49 | 0.761 | 0.000 | 3.17 | | 914.8 | SURCHARGED | |

Appendix C – South Bank Arterial Drainage



HIGH TIP WEST
FOR DETAILS SEE DRAWING No.
TW-SIZ-XX-JBAU-SB-00-DR-C-0002
CHAINAGE 0 - 760m

HIGH TIP NORTH
FOR DETAILS SEE DRAWING No.
TW-SIZ-XX-JBAU-SB-00-DR-C-0003
CHAINAGE 780 - 1220m

INTER TIDAL CHANNEL
FOR DETAILS SEE DRAWING No.
TW-SIZ-XX-JBAU-SB-00-DR-C-0004

| | | | |
|---|---------------------------|--------------------|--------------------|
| 1 | Working near water | Working near water | Working near water |
| 2 | Unknown ground conditions | | |
| 3 | Deep excavations | | |
| 4 | Contaminated ground | | |
| 5 | COMAH site | COMAH site | COMAH site |

| No. | Construction Risk | Maintenance Risk | Demolition Risk |
|-----|-------------------|------------------|-----------------|
|-----|-------------------|------------------|-----------------|

In addition to the hazards/risks normally associated with the types of work detailed on this drawing take note of the above.

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION BOX

Drawing Notes

- This drawing is to be read in conjunction with:-
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0001-Holme_Beck_Key_Plan
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0002-Holme_Beck_General_Arrangement_High_Tip_West
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0003-Holme_Beck_General_Arrangement_High_Tip_North
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0004-Holme_Beck_General_Arrangement_Inter_Tidal_Channel
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0101-Holme_Beck_Long_Section_Sheet_1_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0102-Holme_Beck_Long_Section_Sheet_2_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0103-Holme_Beck_Long_Section_Sheet_3_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0104-Holme_Beck_Long_Section_Sheet_4_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0201-Holme_Beck_Cross_Sections_Sheet_1_of_3
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0202-Holme_Beck_Cross_Sections_Sheet_2_of_3
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0203-Holme_Beck_Cross_Sections_Sheet_3_of_3
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0301-South_Bank_Details_Sheet_1_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0302-South_Bank_Details_Sheet_2_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0303-South_Bank_Details_Sheet_3_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0304-South_Bank_Details_Sheet_4_of_4
- All dimensions are in metres unless noted otherwise.
- All levels are in metres relative to ordnance datum Newlyn (mAOD) unless noted otherwise.
- All coordinates are in metres relative to ordnance survey national grid.
- Do not scale from this drawing. All dimensions must be checked/ verified on site.
- For clarity purposes existing and proposed services have been omitted from this drawing.

| | | | | | | | | | | |
|-----------------------------|----------|--------------------------------|-------|----|----------|----|---------|----|----------|----|
| C02 | Comments | Minor changes | | | | | | | | |
| Rev.: | Date | 17/11/21 | Drawn | MM | Designed | JA | Checked | ST | Approved | RD |
| C01 | Comments | Issued For Planning Permission | | | | | | | | |
| Rev.: | Date | 11/11/21 | Drawn | JN | Designed | JA | Checked | ST | Approved | RD |
| P01 | Comments | First Issue | | | | | | | | |
| Rev.: | Date | 11/10/21 | Drawn | JN | Designed | JA | Checked | ST | Approved | RD |
| Client Approval | | | | | | | | | | |
| A - Approved | | | | | | | | | | |
| B - Approved with Revisions | | | | | | | | | | |
| C - Do Not Use | | | | | | | | | | |

Unit 2.1
Quantum Court
Research Avenue South
Heriot Watt University
EDINBURGH
EH14 4AP
United Kingdom
T +44 (0)131 3192 940
E info@jbaconsulting.com
www.jbaconsulting.com
Twitter @JBAConsulting




Project **South Bank Arterial Drainage**

Title **South Bank Holme Beck Key Plan for**




The property of this drawing and design vested in Jeremy Benn Associates Ltd. It shall not be reproduced in whole or in part, nor disclosed to a third party, without the prior written consent of Jeremy Benn Associates Ltd.


| | | | | | |
|--------------------|--------------------------------|-------------|-----------|------------|------------|
| Drawn: | J. Ness | 06/09/2021 | Designed: | J. Alcock | 06/09/2021 |
| Checked: | S. Thomson | 11/10/2021 | Approved: | R. Dobson | 11/10/2021 |
| Project Reference: | 2021s1087 | | Scale: | 1:2500 @A1 | |
| Drawing Number: | TW-SIZ-XX-JBAU-SB-00-DR-C-0001 | Status: | A1 | Revision: | C02 |
| | | Sheet Size: | A1 | | |



SOUTH BANK CHANNEL - CHAINAGE 0 - 240m



SOUTH BANK CHANNEL - CHAINAGE 240 - 540m



SOUTH BANK CHANNEL - CHAINAGE 540 - 760m

| | | | |
|-----|---------------------------|--------------------|--------------------|
| 1 | Working near water | Working near water | Working near water |
| 2 | Unknown ground conditions | | |
| 3 | Deep excavations | | |
| 4 | Contaminated ground | | |
| 5 | COMAH site | COMAH site | COMAH site |
| No. | Construction Risk | Maintenance Risk | Demolition Risk |

In addition to the hazards/risks normally associated with the types of work detailed on this drawing take note of the above.

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION BOX

Drawing Notes

- This drawing is to be read in conjunction with:-
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0001-Holme_Beck_Key_Key
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0002-Holme_Beck_General_Arrangement_High_Tip_West
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0003-Holme_Beck_General_Arrangement_High_Tip_North
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0004-Holme_Beck_General_Arrangement_Inter_Tidal_Channel
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0101-Holme_Beck_Long_Section_Sheet_1_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0102-Holme_Beck_Long_Section_Sheet_2_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0103-Holme_Beck_Long_Section_Sheet_3_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0104-Holme_Beck_Long_Section_Sheet_4_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0201-Holme_Beck_Cross_Sections_Sheet_1_of_3
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0202-Holme_Beck_Cross_Sections_Sheet_2_of_3
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0203-Holme_Beck_Cross_Sections_Sheet_3_of_3
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0301-South_Bank_Details_Sheet_1_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0302-South_Bank_Details_Sheet_2_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0303-South_Bank_Details_Sheet_3_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0304-South_Bank_Details_Sheet_4_of_4
- All dimensions are in metres unless noted otherwise.
- All levels are in metres relative to ordnance datum Newlyn (mAOD) unless noted otherwise.
- All coordinates are in metres relative to ordnance survey national grid.
- Do not scale from this drawing. All dimensions must be checked/verified on site.
- For clarity purposes existing and proposed services have been omitted from this drawing.

LEGEND

- GABION BASKET RETAINING WALL
- VEGETATED VERGE
- REINFORCED CONCRETE ELEMENT
- 3.5m WIDE VEHICULAR ACCESS TRACK
- POST AND WIRE FENCE
- VEHICULAR ACCESS POINT AND HARDSTANDING
- SERVICE CORRIDOR (DESIGNED BY OTHERS)
- INSITU CONCRETE ELEMENT
- DIRECTION OF FLOW

| | | | | | | | | | | |
|-------|----------|--------------------------------|-------|----|----------|----|---------|----|----------|----|
| C02 | Comments | Minor changes | | | | | | | | |
| Rev.: | Date | 17/11/21 | Drawn | MM | Designed | JA | Checked | ST | Approved | RD |
| C01 | Comments | Issued For Planning Permission | | | | | | | | |
| Rev.: | Date | 11/11/21 | Drawn | JN | Designed | JA | Checked | ST | Approved | RD |

Client Approval

- A - Approved
- B - Approved with Revisions
- C - Do Not Use

Unit 2.1
Quantum Court
Research Avenue South
Heriot Watt University
EDINBURGH
EH14 4AP
United Kingdom
T +44 (0)131 3192 940
E info@jbaconsulting.com
www.jbaconsulting.com
Twitter @JBAConsulting




Project
South Bank Arterial Drainage

Title
South Bank
Holme Beck - High Tip West
General Arrangement
for


Client
TEESWORKS

The property of this drawing and design vested in Jeremy Benn Associates Ltd. It shall not be reproduced in whole or in part, nor disclosed to a third party, without the prior written consent of Jeremy Benn Associates Ltd.


| | | | | | |
|--------------------|--------------------------------|-------------|-----------|-----------|------------|
| Drawn: | J. Ness | 06/09/2021 | Designed: | J. Alcock | 06/09/2021 |
| Checked: | S. Thomson | 11/10/2021 | Approved: | R. Dobson | 11/10/2021 |
| Project Reference: | 2021s1087 | Scale: | 1:500 @A1 | | |
| Drawing Number: | TW-SIZ-XX-JBAU-SB-00-DR-C-0002 | Status: | A1 | Revision: | C02 |
| | | Sheet Size: | A1 | | |



SOUTH BANK CHANNEL - CHAINAGE 780 - 1080m



SOUTH BANK CHANNEL - CHAINAGE 1080 - 1220m



SOUTH BANK CHANNEL - CHAINAGE 1080 - 1220m

| | | | |
|---|---------------------------|--------------------|--------------------|
| 1 | Working near water | Working near water | Working near water |
| 2 | Unknown ground conditions | | |
| 3 | Deep excavations | | |
| 4 | Contaminated ground | | |
| 5 | COMAH site | COMAH site | COMAH site |

| No. | Construction Risk | Maintenance Risk | Demolition Risk |
|-----|-------------------|------------------|-----------------|
|-----|-------------------|------------------|-----------------|

In addition to the hazards/risks normally associated with the types of work detailed on this drawing take note of the above.

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION BOX

- Drawing Notes**
- This drawing is to be read in conjunction with:-
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0001-Holme_Beck_Key_Plan
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0002-Holme_Beck_General_Arrangement_High_Tip_West
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0003-Holme_Beck_General_Arrangement_High_Tip_North
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0004-Holme_Beck_General_Arrangement_Inter_Tidal_Channel
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0101-Holme_Beck_Long_Section_Sheet_1_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0102-Holme_Beck_Long_Section_Sheet_2_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0103-Holme_Beck_Long_Section_Sheet_3_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0104-Holme_Beck_Long_Section_Sheet_4_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0201-Holme_Beck_Cross_Sections_Sheet_1_of_3
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0202-Holme_Beck_Cross_Sections_Sheet_2_of_3
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0203-Holme_Beck_Cross_Sections_Sheet_3_of_3
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0301-South_Bank_Details_Sheet_1_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0302-South_Bank_Details_Sheet_2_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0303-South_Bank_Details_Sheet_3_of_4
 - TW-SIZ-XX-JBAU-SB-00-DR-C-0304-South_Bank_Details_Sheet_4_of_4
 - All dimensions are in metres unless noted otherwise.
 - All levels are in metres relative to ordnance datum Newlyn (mAOD) unless noted otherwise.
 - All coordinates are in metres relative to ordnance survey national grid.
 - Do not scale from this drawing. All dimensions must be checked/verified on site.
 - For clarity purposes existing and proposed services have been omitted from this drawing.

LEGEND

- GABION BASKET RETAINING WALL
- VEGETATED VERGE
- REINFORCED CONCRETE ELEMENT
- 3.5m WIDE VEHICULAR ACCESS TRACK
- POST AND WIRE FENCE
- VEHICULAR ACCESS POINT AND HARDSTANDING
- SERVICE CORRIDOR (DESIGNED BY OTHERS)
- INSITU CONCRETE ELEMENT
- DIRECTION OF FLOW

| | | | | | | | | | | |
|-------|----------|--------------------------------|-------|----|----------|----|---------|----|----------|----|
| C02 | Comments | Minor changes | | | | | | | | |
| Rev.: | Date | 17/11/21 | Drawn | MM | Designed | JA | Checked | ST | Approved | RD |
| C01 | Comments | Issued For Planning Permission | | | | | | | | |
| Rev.: | Date | 11/11/21 | Drawn | JN | Designed | JA | Checked | ST | Approved | RD |

Client Approval
 A - Approved
 B - Approved with Revisions
 C - Do Not Use

Unit 2.1
 Quantum Court
 Research Avenue South
 Heriot Watt University
 EDINBURGH
 EH14 4AP
 United Kingdom
 T +44 (0)131 3192 940
 E info@jbaconsulting.com
 www.jbaconsulting.com
 Twitter @JBAConsulting



Project
 South Bank Arterial Drainage

Title
 South Bank
 Holme Beck - High Tip North
 General Arrangement
 for

Client

The property of this drawing and design vested in Jeremy Benn Associates Ltd. It shall not be reproduced in whole or in part, nor disclosed to a third party, without the prior written consent of Jeremy Benn Associates Ltd.

| | | | | | |
|--------------------|--------------------------------|-------------|-----------|-----------|------------|
| Drawn: | J. Ness | 06/09/2021 | Designed: | J. Alcock | 06/09/2021 |
| Checked: | S. Thomson | 11/10/2021 | Approved: | R. Dobson | 11/10/2021 |
| Project Reference: | 2021s1087 | Scale: | 1:500 @A1 | | |
| Drawing Number: | TW-SIZ-XX-JBAU-SB-00-DR-C-0003 | Status: | A1 | Revision: | C02 |
| | | Sheet Size: | A1 | | |